

IBM BladeCenter Foundation for Cloud Site Requirements Document (SRD)

To ensure a successful installation of an IBM BladeCenter Foundation for Cloud 42U rack configuration, this document outlines key information for the Site Facilities team. *Note:* It's critical for the Facilities Coordinator at the customer site to review this information in advance to ensure that the site is enabled prior to delivery of the IBM solution.

This document only covers physical infrastructure requirements and assumes a separate analysis has been conducted to assess the suitability of the rack configuration for particular workloads.

The following table summarizes the physical characteristics of the equipment based on the size of the configuration (Small, Medium, Large), including hardware power and cooling requirements.

| | Small | Medium | Large |
|---|---|---|---|
| # of Blades | 4 Blades | 5 - 14 Blades | 15 - 28 Blades |
| Current (@200V) | 43.11A | 47.01A | 90.09 A |
| # of Racks | 1 | 1 | 1 |
| Max Power Load | 10748 W | 11468 W | 22168 W |
| Power and Number of PDUs, Customer provided receptacles | (2) PDUs (2) power receptacles meeting appropriate country standards (i.e., For US, 60 AMP Single Phase power receptacles IEC 309 2P+G) | (4) PDUs (4) power receptacles meeting appropriate country standards (i.e., For US, 60 AMP Single Phase power receptacles IEC 309 2P+G) | (6) PDUs (6) power receptacles meeting appropriate country standards (i.e., For US, 60 AMP Single Phase power receptacles IEC 309 2P+G) |
| Total BTU | 36652 btu/hr | 39112 btu/hr | 75648 btu/hr |
| Max. Customer Cable Connections | (2) 1G Ethernet, (4) 10G Ethernet fiber, (4) 8G FC 518 kg | (2) 1G Ethernet, (6) 10G Ethernet fiber, (4) 8G FC 594 kg | (2) 1G Ethernet, (12) 10G Ethernet fiber, (4) 8G FC 874 kg |
| Total Weight | 310 kg | 594 kg | 074 Kg |
| Rack Dimensions (HxWxD) | 2020 x 648 x 1105 mm (79.5 x 25.5 x 43.5 in) | | |
| Palletized Dimensions (HxWxD) | 2210 x 818 x 1295 mm (87.0 x 32.2 x 51.0 in) | | |
| Pallet Weight | 950kg. (Max) | | |

Notes:



- Loading docks, doorways, passageways and elevators should be of sufficient capacity to allow receipt and delivery of the rack to the final location of installation.
- All cables will exit the bottom of the rack.

If there are concerns associated with these requirements, please contact your IBM Sales Team... thank you!

Figure 1 illustrates the layout of the components included in the IBM BladeCenter Foundation for Cloud rack (Large configuration shown). The layout of the rack solution delivered to your site may vary based on your specific configuration. Also note that line cord connectors will exit the bottom of the rack and vary by country. Figure 1 shows an example for the U.S.




Figure 1: Example of Small IBM BladeCenter Foundation for Cloud Rack





Figure 2: Example of Medium IBM BladeCenter Foundation for Cloud Rack





4 PDUs are in this configuration. Customer must supply 4 receptacles per below;

Power Distribution Unit Line Cord Connector and Receptacle

IEC 309 2P+G
Single Phase
Anpere 50A
Voltage: 208Vac

Receptacle Supplied by Customer

Receptacle Supplied by Customer

Figure 4: Example of IBM BladeCenter Foundation for Cloud Rack US Cord Connectors

Figure 3: Example of Large IBM BladeCenter Foundation for Cloud Rack

If you experience any technical issues with IBM BladeCenter Foundation for Cloud Rack and require assistance, please contact IBM Support (http://www-03.ibm.com/systems/bladecenter/support/).