

# User's Guide

Version 4.10



# User's Guide

Version 4.10

Note	
Before using this information and the product it supports, read the information in "Notices" on page 65.	
This edition applies to version 3.1 of the IBM UpdateXpress System Pack Installer and to all subsequent rend modifications until otherwise indicated in new editions.	leases

© Copyright IBM Corporation 2004, 2010. US Government Users Restricted Rights – Use, duplication or disclosure restricted by GSA ADP Schedule Contract with IBM Corp.

## Contents

Figures	Using the CLI
<b>-</b>	Compare and Update
Tables vii	Using the CLI
	Using the GUI
About this guide ix	Update BladeCenter
Accessibility ix	Acquiring MM and I/O modules
Accessibility features for UpdateXpress System	Using the CLI
Pack Installer ix	
Who should read this guide $\ldots \ldots x$	Chapter 6. UpdateXpress System Pack
Nove in consists 4.40	Installer scenarios 37
New in version 4.10 xi	Updating a local machine from the IBM Web site 37
	Updating a local machine from a local directory 38
Chapter 1. Technical overview of	Creating a repository of updates
UpdateXpress System Pack Installer 1	Non-interactive local deployment using CLI 39
	Interactive local deployment using CLI 41
Chapter 2. Web resources 3	Customizing UpdateXpress System Pack using CLI 42
	Updating from removable media (non-bootable) 43
Chapter 3. Concepts 5	Updating firmware for an IBM BladeCenter RAID
UpdateXpress System Pack 5	SAS switch module
How UpdateXpress System Pack Installer applies	Acquiring the latest updates for a particular type of
updates 5	update
Handling an UpdateXpress System Pack as a bundle 6	Chapter 7 Troublesheeting 47
Identify update packages that cannot be applied 6	Chapter 7. Troubleshooting 47
Missing or incomplete inventory data 6	Limitations and problems
Installing required drivers 6	Return codes
0	UpdateXpress System Pack Installer return codes 58
Chapter 4. Requirements 9	UpdateXpress System Pack Installer deployment
Supported hardware components 9	return values 60
Supported operating systems	
Windows	Chapter 8. Coexistence and
VMware	compatibility 63
Operating system privileges	, , , ,
e perming eyetem privileges in the internal control of	Notices
Chapter 5. Using UpdateXpress System	Trademarks
Pack Installer	iradeliaira
The UpdateXpress System Pack Installer user	Glossary 69
interfaces	
Command-line interface	Index
GUI	
Acquire Updates	

				_	_
FI	a	u	r	e	S
	J	9	•	_	_

1.	CLI - Screen displ	av					. 18	2	2.	CLI - Interactive commands		. 20

## **Tables**

1.	Supported Windows operating systems	11	5.	UpdateXpress System Pack Installer return	
2.	Supported Linux operating systems	12		codes	. 58
	VMware support		6.	UpdateXpress System Pack Installer	
4.	Data displayed on screen after CLI input	21		deployment return values	. 60

## About this guide

IBM<sup>®</sup> UpdateXpress System Pack Installer is a software application that applies UpdateXpress System Packs and individual updates to your system.

The purpose of this guide is to describe the UpdateXpress System Pack Installer software deliverable. It includes:

- Descriptions of the physical components that comprise the software.
- Descriptions of its user interfaces.

## Accessibility

IBM strives to provide products with usable access for everyone, regardless of age or ability.

## Accessibility features for UpdateXpress System Pack Installer

Accessibility features help users who have a disability, such as restricted mobility or limited vision, to use information technology products successfully.

#### **Accessibility features**

The following list includes the major accessibility features in IBM UpdateXpress System Pack Installer:

- Keyboard-only operation
- Interfaces that are commonly used by screen readers

The UpdateXpress System Pack Installer topic collection in the IBM System x ToolsCenter information center, and its related publications, are accessibility-enabled.

### Keyboard navigation

The command line interface (CLI) is controlled by the keyboard. For more information, see "Command-line interface" on page 16.

You can use the following keyboard shortcuts from the graphical user interface:

Shortcut (Linux®)	Shortcut ( Windows®)	Action
Alt+C	Alt+C	Close the graphical user interface.
Alt+N	Alt+N	Go to the next page.
Alt+P	Alt+P	Go to the previous page.
Tab	Tab	Go to the next control.
Shift+Tab	Shift+Tab	Move to the previous control.
Left arrow	Left arrow	Move back one character.
Right arrow	Right arrow	Move forward one character.
Backspace	Backspace	Delete the character to the left of the cursor.

Shortcut (Linux®)	Shortcut ( Windows®)	Action
Delete	Delete	Delete the character under the cursor.
Up arrow	Up arrow	Move focus and selection upwards through the radio buttons.
Down arrow	Down arrow	Move focus and selection downwards through the radio buttons.
Space	Space	Select or clear an option.

### IBM and accessibility

For more information about the commitment that IBM has to accessibility, see IBM Human Ability and Accessibility Center on the Web at www.ibm.com/able.

## Who should read this guide

This guide is for system administrators or other individuals responsible for system administration who are familiar with firmware and device driver maintenance.

### New in version 4.10

UpdateXpress System Pack Installer, v4.10 provides a number of enhancements since the previous release, v4.01.

#### Support for additional operating systems

The following operating systems are now supported by UpdateXpress System Pack Installer, v4.10:

- SuSE Linux Enterprise Server 11 SP1
- Red Hat Enterprise Linux 5U5
- VMware ESX 4.0u2

For complete operating system support information, see "Supported operating systems" on page 11.

#### Support for additional hardware

The following hardware is now supported by UpdateXpress System Pack Installer, v4.10:

- IBM System x<sup>®</sup>3400 M3
- IBM System x3500 M3
- IBM System x3550 M3
- IBM System x3620 M3
- IBM System x3650 M3
- IBM System x3690 X5
- IBM System x3850 X5
- IBM System x3950 X5
- IBM BladeCenter<sup>®</sup> HS22V
- IBM BladeCenter HX5
- IBM iDataPlex<sup>™</sup> dx360 M3

For complete hardware support information, see "Supported hardware components" on page 9.

#### Consolidated function

Beginning in version 4.10, the IBM ToolsCenter Bootable Media Creator is no longer packaged with the UpdateXpress System Pack Installer. The Bootable Media Creator is available for download at: http://www-947.ibm.com/systems/support/supportsite.wss/docdisplay?lndocid=TOOL-BOMC&brandind=5000016

## Chapter 1. Technical overview of UpdateXpress System Pack Installer

UpdateXpress System Pack Installer deploys UpdateXpress System Pack and individual updates.

UpdateXpress System Packs contain Windows and Linux firmware and device driver updates. UpdateXpress System Pack Installer allows you to acquire and deploy these updates, as well as individual updates.

The three main functions of UpdateXpress System Pack Installer are:

#### **Acquire Updates**

The Acquire Updates function allows you to download UpdateXpress System Pack and individual updates for supported machine types from a remote location, such as IBM support.

#### Compare and Update

The Compare and Update functions inventory the system on which the update will be performed, query the update directory for a list of applicable update packages, compare the inventory to the applicable update list, recommend a set of updates to apply, and then deploy those updates to the system.

#### Update BladeCenter

The **bladecenter** command provides the capability to update the BladeCenter Management Module, the I/O Modules and the RSSM infrastructure.

## Chapter 2. Web resources

The following Web pages provide resources for understanding, using, and troubleshooting IBM System x and systems-management tools.

#### Web sites

#### IBM ToolsCenter for System x and BladeCenter

www.ibm.com/systems/support/supportsite.wss/docdisplay?lndocid=TOOL-CENTER&brandind=5000016

View this Web site to download tools that support IBM System x and IBM BladeCenter products.

#### UpdateXpress

www.ibm.com/systems/support/supportsite.wss/docdisplay?lndocid=SERV-XPRESS&brandind=5000016

View this Web site to download the tool, UpdateXpress System Pack libraries and tools, including UpdateXpress System Pack Installer.

#### · Support for IBM BladeCenter

www-304.ibm.com/systems/support/supportsite.wss/brandmain?brandind=5000020

View this Web site to find information about online technical support, downloads and drivers, and RETAIN® tips, and to provide feedback about IBM BladeCenter products.

#### Support for IBM System x

www-304.ibm.com/jct01004c/systems/support/supportsite.wss/brandmain?brandind=5000008

View this Web site to find information about online technical support, downloads and drivers, and RETAIN tips, and to provide feedback about IBM System x products.

#### IBM ServerProven<sup>®</sup>

www.ibm.com/servers/eserver/serverproven/compat/us/

View this Web site to learn about hardware compatibility of IBM System x and IBM BladeCenter systems with IBM applications and middleware.

#### **Forums**

#### • IBM System x Forum

www.ibm.com/developerworks/forums/forum.jspa?forumID=740

View this Web site on ibm.com<sup>®</sup> to learn about various forums that are available to discuss technology-related and product-related issues pertaining to IBM System x hardware and software products. This Web site includes a link for obtaining the forum using a Rich Site Summary (RSS) feed.

#### • IBM BladeCenter Forum

www.ibm.com/developerworks/forums/forum.jspa?forumID=819

View this Web site on ibm.com to learn about various forums that are available to discuss technology-related and product-related issues pertaining to IBM BladeCenter hardware and software products. This Web site includes a link for obtaining the forum using a Rich Site Summary (RSS) feed.

## **Chapter 3. Concepts**

This section discusses concepts concerning how UpdateXpress System Pack Installer works, to help you use UpdateXpress System Pack Installer most effectively.

## **UpdateXpress System Pack**

An *UpdateXpress System Pack* (UXSP) is an integration-tested bundle of online firmware and driver updates for IBM System x and IBM BladeCenter servers.

UpdateXpress System Packs simplify the downloading and installation of all online driver and firmware updates for a given system, ensuring that you are always working with a complete, current set of updates that have been tested together and bundled by IBM.

UpdateXpress System Packs are created for a machine type and operating system combination. Separate UpdateXpress System Packs are provided for Windows and each of the Linux distributions. For example, there could be several UpdateXpress System Packs for one particular machine type. There might be one for Windows, and then one for each Linux distribution. UpdateXpress System Packs are generally released semiannually for the first three years, and annually for the final three years of support.

#### **UXSP** format

A UXSP is delivered as an XML file. The naming convention for a UXSP takes on the following format: ibm\_utl\_uxsp\_version\_operatingsystem\_arch.xml. **Example**: ibm\_utl\_uxsp\_a3sp27a-1.00\_windows\_32-64.xml.

## How UpdateXpress System Pack Installer applies updates

Regardless of whether you run UpdateXpress System Pack Installer from the command-line interface (CLI) or the graphical user interface (GUI), you need to follow the same step-by-step process:

- 1. Download the UpdateXpress System Pack Installer from the IBM web site.
- 2. Use the installer to acquire the UpdateXpress System Pack for the desired machine-type/operating system combination into a local or network-shared directory.
- 3. Run the installer.

**Note:** You may also download the updates directly from the IBM Web site. Just remember to download the update payload as well as the XML file.

For convenience choose the same destination directory for each UpdateXpress System Pack download, otherwise you will have to specify the destination directory with the -I command line argument. You can download multiple system packs for different machine-types into the same directory. When you run the installer, it detects the machine-type and uses the correct content for the machine-type. In some cases, there may be common files between system packs. Common files that are already present in the directory will not be downloaded again and the overall download time will be reduced.

You use the UpdateXpress System Pack Installer to apply UpdateXpress System Pack updates to your system. UpdateXpress System Pack Installer inventories the system on which the update will be performed, queries a specified location for a list of applicable update packages, compares the inventory to the applicable update list, recommends a set of updates to apply, and then deploys those updates to the system.

The tasks can be performed two ways:

- 1. As an **update**, which performs all four tasks.
- 2. As a **compare**, which performs only the first 3 tasks: inventory, query, and compare.

For more information on compare and update, see "Compare and Update" on page 25.

## Handling an UpdateXpress System Pack as a bundle

UpdateXpress System Pack Installer is designed to download and apply UpdateXpress System Packs. The System Pack is a collection of individual updates as specified by the UpdateXpress System Pack XML. When running the Installer tool from the CLI, the tool downloads and applies System Packs by default. If you wish to work with individual updates, you need to specify the -L (--latest) argument. When running the Installer tool from the GUI, you are given the option to select either UpdateXpress System Packs or Individual Updates. In most cases it is recommended to work with UpdateXpress System Packs, but the option to also work with individual updates gives you the greatest flexibility in choosing which updates to use.

## Identify update packages that cannot be applied

Individual updates might include update packages that UpdateXpress System Pack Installer cannot apply. Some examples of these update packages are CPLD firmware, and other legacy Symantec packages. If the UpdateXpress System Pack Installer encounters one of these updates, it displays a warning message Warning: offline update *filename* detected, will not apply, where filename corresponds to the name of the update and the update is ignored.

## Missing or incomplete inventory data

Sometimes, an update package applies to a component for which UpdateXpress System Pack Installer cannot determine the system version. In this case, UpdateXpress System Pack Installer displays no value for the system version, displays the version of the update package, and selects the package as a recommended update. The installer displays Undetected when no installed version is detected.

## Installing required drivers

UpdateXpress System Pack Installer installs device drivers.

#### **About this task**

UpdateXpress System Pack Installer installs every driver in the UpdateXpress System Pack when:

- 1. The current device driver is detected to be at an earlier version than the available driver in the UpdateXpress System Pack, or
- 2. The UpdateXpress System Pack Installer is unable to determine the current device driver version, which typically occurs when the device driver is not installed.

Note: The installer displays Undetected when no installed version is detected.

You can take advantage of this behavior to install the following device drivers, which are required for firmware updates:

- Intelligent Peripheral Management Interface (IPMI)
- IPMI Mapping Layer
- Remote Supervisor Adapter II (RSAII)

## **Chapter 4. Requirements**

Before you begin using UpdateXpress System Pack Installer, review the hardware and operating system support, as well as the local operating system privilege requirements.

## **Supported hardware components**

UpdateXpress System Pack Installer supports Windows and Linux device drivers and firmware that are included in available UpdateXpress System Packs. A current list of supported components (device drivers and firmware) can be found in the UpdateXpress System Pack readme file that is included with each system pack.

The following table lists IBM systems that are supported by UpdateXpress System Pack Installer. It also shows which systems support the latest UXSPs (indicated by "yes" in the third column) and which systems support only individual updates (indicated by "no" in the third column).

Server	Machine Type	UXSP support
System x 206m	8485, 8490	No
System x 226	8488, 8648	No
System x 236	8841	No
System x 3800	8866	Yes
System x 336	1879, 8837	No
System x 3850	8863	Yes
System x 460	8872	Yes
System x 460 MXE	7363, 8872	Yes
System x 3200	4362, 4363	Yes
System x 3200 M2	4367, 4368	Yes
System x 3200 M3	7327, 7328	Yes
System x 3250	4364, 4365, 4366	Yes
System x 3250 M2	4190, 4191, 4194	Yes
System x 3250 M3	4251, 4252, 4261	Yes
System x 3350	4192, 4193	Yes
System x 3400	7973, 7974, 7975, 7976	Yes
System x3400 M2	7836, 7837	Yes
System x3400 M3	7378, 7379	Yes
System x 3450	7948, 4197	Yes
System x 3455	7984, 7986, 7940, 7941	Yes
System x 3500	7977	Yes
System x 3500 M2	7839	Yes
System x 3500 M3	7380	Yes
System x 3550	1013, 1913 , 7978	Yes
System x 3550 M2	4198, 7946	Yes

Server	Machine Type	UXSP support
System x 3550 M3	4254, 7944	Yes
System x 3620 M3	7376	Yes
System x 3650	7979, 1914	Yes
System x 3650 M2	4199, 7947	Yes
System x 3650 M3	4255, 7945	Yes
System x 3655	7943, 7985	Yes
System x 3690 X5	7148, 7149	Yes
System x 3755	8877, 7163	Yes
System x 3800	8866	Yes
System x 3850	8864, 7365, 7362	Yes
System x 3850 M2 and System x 3950 M2	7141, 7144, 7233, 7234	Yes
System x 3850 X5	7145	Yes
System x 3950	7363, 7366, 8872, 8874, 8878	Yes
System x 3950 E	7364, 7367, 8874, 8879	Yes
System x 3950 M2 2-4 node	7141, 7233, 7234	Yes
System x 3950 X5	7146	Yes
BladeCenter HS12	8014, 8028, 1916	Yes
BladeCenter HS20	1883, 8843	Yes
BladeCenter HS21	1885, 8853	Yes
BladeCenter HS21 XM	1915, 7995	Yes
BladeCenter HS22	1936, 7809, 7870	Yes
BladeCenter HS22V	1949, 7871	Yes
BladeCenter HX5	1909, 7872	Yes
BladeCenter LS20	8850	Yes
BladeCenter LS21	7971	Yes
BladeCenter LS22	7901	Yes
BladeCenter LS42	7902	Yes
BladeCenter LS41	7972	Yes
iDataPlex dx320	6388	Yes
iDataPlex dx340	6389, 7832, 7834	Yes
iDataPlex dx360	6316, 6390, 7833	Yes
iDataPlex dx360 M2	6380, 7321, 7323	Yes
iDataPlex dx360 M3	6391	Yes

#### Notes:

- System x 3450 does not detect all firmware, specifically BIOS and BMC update; however, you can use UpdateXpress System Pack Installer to update the BIOS/BMC image.
- System x 3850 M2 and System x 3950 M2 are supported in single node as well as multi node.

• System x 460, MXE-460 and System x 3950 are supported only in single node. To update a multi-node system, you must break apart the nodes and update as single nodes.

#### **Unsupported systems**

The following systems are not supported by UXSP Installer:

Server	Machine Type	
eServer <sup>™</sup> 326	8848	
eServer 326m	7969, 7992	
System x 100	8486	
System x 206	8482, 8487	
System x 306	1878, 8836, 8489	
System x 325	8671	
System x 335	8676	
System x 345	8670	
BladeCenter HS20	7981, 8832	
BladeCenter HS40	8839	

For details on how UpdateXpress System Pack Installer applies updates, see "How UpdateXpress System Pack Installer applies updates" on page 5.

## Supported operating systems

UpdateXpress System Pack Installer is supported on Linux and Windows operating systems, as well as on VMware ESX Server 3.0/3.5/4.0. UpdateXpress System Pack Installer, v4.10, is supported on both 32-bit and 64-bit operating systems.

You may need to determine which operating systems your server supports. This information can found on the www.ibm.com/servers/ Web site (http://www.ibm.com/servers/).

#### **Windows**

UpdateXpress System Pack Installer is supported on Windows operating systems.

Table 1. Supported Windows operating systems

Operating system	Acquire Updates	Compare/Update
Windows Storage Server 2003 / 2003 R2	х	х
Windows Small Business Server 2003 / 2003 R2 • Standard Edition [SE] • Professional Edition [PE]	х	х
Windows Server 2003 / 2003 R2  • Standard Edition [SE]  • Enterprise Edition [EE]	х	х
Windows Server 2008	Х	Х
Windows Server 2008 R2	Х	Х
Windows 2008 Server Core <sup>2</sup>		Х

Table 1. Supported Windows operating systems (continued)

Operating system	Acquire Updates	Compare/Update
Microsoft® Hyper-V Server 2008		x
Windows Server 2008 R2 <sup>1</sup>	х	X
Windows Server 2008 Core R2 <sup>1,2</sup>		X
Windows XP Business Edition	X	
Windows Vista	X	
Windows 7	х	

- 1. x64 support requires WOW.
- 2. The GUI can be used only from a non-Server Core Windows operating system. You can compare and push updates to Server Core systems over the network using the CLI --remote command. See the CLI commands for usage and details.

In v4.10 of the installer, the Windows executable is named: uxspi410.exe

#### Linux

UpdateXpress System Pack Installer is supported on Linux operating systems.

Table 2. Supported Linux operating systems

Operating system	Executable file
RHEL 3.0 x86  • Entry Server [ES]  • Advanced Server [AS]  • Workstation Server [WS]	uxspi410.rhel3
RHEL 3.0 AMD64/EM64T  • Entry Server [ES]  • Advanced Server [AS]  • Workstation Server [WS]	uxspi410.rhel3
RHEL 4.0 x86  • Entry Server [ES]  • Advanced Server [AS]  • Workstation Server [WS]	uxspi410.rhel4
RHEL 4.0 AMD64/EM64T  • Entry Server [ES]  • Advanced Server [AS]  • Workstation Server [WS]	uxspi410.rhel4
RHEL 5.0 x86 with and without XEN component  • Entry Server [ES]  • Advanced Server [AS]  • Workstation Server [WS]	uxspi410.rhel5
RHEL 5.0 AMD64/EM64T with and without XEN component • Entry Server [ES] • Advanced Server [AS] • Workstation Server [WS]	uxspi410.rhel5
SLES 9.0 x86	uxspi410.sles9
SLES 9.0 AMD64/EM64T	uxspi410.sles9
SLES 10.0 x86 with and without XEN component	uxspi410.sles10

Table 2. Supported Linux operating systems (continued)

Operating system	Executable file
SLES 10.0 AMD64/EM64T with and without Xen component	uxspi410.sles10
SLES 11.0 x86 with and without XEN component	uxspi410.sles11
SLES 11.0 AMD64/EM64T with and without XEN component	uxspi410.sles11

**Note:** Linux device driver updates require specific packages. The Linux device driver update packs require the following packages to be installed:

- rpm-build, perl, and bash for Redhat Enterprise Linux
- perl and bash for SuSE Enterprise Linux

#### **VMware**

UpdateXpress System Pack Installer is supported on VMware.

Table 3. VMware support

Operating system	Executable file
VMware ESX Server 3.0	uxspi410.rhel3
VMware ESX Server 3i (bootside update only)	uxspi410.rhel3
VMware ESX Server 3.5	uxspi410.rhel3
VMware ESX Server 4.0	uxspi410.rhel5

#### Note:

- VMware ESX Server 3.0 and 3.5 are not available in 64-bit.
- To use the remote functions of VMware ESX server, you must make specific adjustments to your configuration. These adjustments are detailed in Additional considerations when using VMware ESX remote functions in "Limitations and problems" on page 47.

## Operating system privileges

In order to run UpdateXpress System Pack Installer, you must have administrator or root equivalent operating system privileges. UpdateXpress System Pack Installer returns an error if a user with insufficient privileges attempts to run it.

## Chapter 5. Using UpdateXpress System Pack Installer

To run UpdateXpress System Pack Installer, invoke the executable file for your operating system. No installation is required to run UpdateXpress System Pack Installer. You can invoke the UpdateXpress System Pack Installer executable file from a command-line interface or a graphical user interface (GUI).

#### Windows

In v4.10 of the installer, the Windows executable file is named: uxspi410.exe

For each release of the installer, you can distinguish the Windows executable file name by its version number. The Windows executable file is specified on the command line as **uxspiversion.exe**, where uxspi is the name of the executable file and *version* indicates the installer version number.

#### Linux

In v4.10 of the installer, the Linux executable files are named:

uxspi410.rhel3 uxspi410.rhel4 uxspi410.rhel5 uxspi410.sles9 uxspi410.sles10 uxspi410.sles11

For each release of the installer, you can distinguish the Linux executable files by their version number. Linux executable files are indicated on the command line as **uxspiversion.LinuxOS**, where uxspi is the name of the executable file, *version* indicates the installer version number, and **LinuxOS** is the Linux operating system name. For example, the executable file names for V3.0.2 are:

```
uxspi302.rhel3
uxspi302.rhel4
uxspi302.rhel5
uxspi302.sles9
uxspi302.sles10
```

#### **VMware**

In v4.10of the installer, the executable file for VMware ESX Server 3.0 and 3.5 is named:

uxspi410.rhel3

and the executable file for VMWare ESX Server 4 is named: uxspi410.rhe15

In this documentation, **<program>** is used to refer to the name of the UpdateXpress System Pack Installer executable file. **file which supports all of the supported Windows operating systems, or the Linux executable files which support the supported Linux operating systems. See "Supported operating systems" on page 11 for complete OS support.** 

## The UpdateXpress System Pack Installer user interfaces

You can access UpdateXpress System Pack Installer functions through a command-line interface or a graphical user interface.

#### **Functional differences**

While the UpdateXpress System Pack Installer command-line interface and GUI contain nearly the same functional capabilities, there are some functions that are available in the CLI - and not in the GUI. Only when using the command-line interface can you direct the installer to:

- Run unattended in a scriptable environment.
- Customize a UXSP by including or excluding specific updates.
- Acquire an individual update by specifying the update filename.
- Perform updates on remote systems
- Perform updates to IBM BladeCenter systems

#### **Command-line interface**

You can run UpdateXpress System Pack Installer by specifying commands and options in the CLI.

The general syntax for typing UpdateXpress System Pack Installer commands in the CLI is as follows:

```
ommand> [common options] [command options]
```

- "Acquire Updates" on page 23
- "Compare and Update" on page 25
- "Update BladeCenter" on page 30

#### [common options]

The following options are available to use with the Windows and Linux versions of UpdateXpress System Pack Installer:

#### --command-help

Displays the specific usage information for specified command. You can specify one of these commands:

- --acquire-help
- --bladecenter-help
- --update-help
- --compare-help

#### -c file | --commands=file

Specifies an optional command file that is used to specify additional command arguments. The arguments contained in the command file have the exact same syntax as the command arguments with the exception that a new line is interpreted as a space character. This new line exception means that arguments in the command file may be specified on multiple lines. An example of a command file used for acquisition is:

```
-m 8843,8850,7983,7971,4364,4362,4347
```

- -o rhel4, rhel5, windows
- -1 groups1-2-3

#### -h | --help | -?

Displays help in the current console window and exit.

Note: You cannot specify other options with this option.

#### --license

Displays license information. You can output this information to a file using the > redirect character.

#### -u | --unattended

Runs UXSPI in unattended mode. This is non-interactive, but will display messages to standard output.

#### -V | --version

Displays the version of UpdateXpress System Pack Installer in the current console window and exit.

Note: You cannot specify other options with this option.

### Screen display and CLI input

The UpdateXpress System Pack Installer CLI screen displays information in two formats:




Figure 1. CLI - Screen display

The first format is for updates that include individual update files. In this format, you see the package data and the individual update file data:

```
[*] IBM ServeRAID 8i, 8k, 8k-1, 8s Controller Driver
   Severity
                         : Recommended
                         : Reboot required to take effect
   Reboot
   Update ID
                         : ibm dd aacraid 5.2.0.11829 windows 32-64
   Update
                         : arcsas.sys
                       : 5.2.0.11829
   New Version
   Installed Version
                         : 5.1.0.10170
```

When there are updates associated with multiple driver files, all of the installed driver files and version are displayed. For example the MPTSAS driver on Linux may display similar to the following:

[\*] IBM and LSI Basic or Integrated RAID SAS Controller Driver

Severity : Recommended
Reboot : Reboot Required to take effect
Update ID : ibm\_dd\_mptsas\_4.00.21.00\_sles10\_32-64

Update : mptscsih.ko
New Version : 4.00.21.00 Installed Version : 3.04.02-suse

Update : mptbase.ko New Version : 4.00.21.00 Installed Version : 3.04.02-suse

Update : mptctl.ko New Version : 4.00.21.00 Installed Version : 3.04.02-suse

Update : mptfc.ko New Version : 4.00.21.00 Installed Version : 3.04.02-suse

Update : mptlan.ko New Version : 4.00.21.00 Installed Version : 3.04.02-suse

Update : mptsas.ko New Version : 4.00.21.00 Installed Version: 3.04.02-suse

Update : mptspi.ko
New Version : 4.00.21.00 Installed Version : 3.04.02-suse

The second format is for updates that do not include data about individual update files:

[\*] RSA II Daemon for IA32 Windows

Severity : Recommended
Reboot : Reboot required to take effect
Update ID : ibm\_svc\_rsa2\_hlp416a\_winsrvr\_i386
New Version : 5.40
Installed Version : Undetected

```
Command Prompt
                                                                                                   _ 🗆 ×
(14) [ ] Online Broadcom NetXtreme and NetXtreme II Firmware Update Utility
                                  : Non-Critical
: Not Required
           Severity
           Reboot
          Update ID
                                    : brcm_fw_nic_2.0.3_windows_32-64
          Update
                                   : b8c1 (#1)
          New Version
                                      3.4.4
           Installed Version
                                    : b8c1 (#2)
          New Version
                                      3.4.4
           Installed Version : 3.4.4
(15) [ ] eServer System x3755 BMC Update
           Severity
                                   : Recommended
          Reboot : Reboot Required to take effect
Update ID : ibm_fw_bmc_zybt42a_windows_i386
New Version : 1.05 (ZYBT42A)
Installed Version : 1.05 (ZYBT42A)
(16) [*] MegaRAID 8480 SAS Controller Firmware
                                   : Recommended
           Severity
           Reboot
                                      Reboot Required to take effect
                                   : lsi_fw_megasas_1.03.00-0225_windows_32-64
: 1.03.00-0225
          Update ID
           New Version
           Installed Version : Undetected
Legend:
Type the item number to toggle selected [*] or not selected [ ]
Type 'a' to accept the menu
Type 'f' to select all entries
Type 'q' to guit without processing the entries
[1-16,a,q,f]>
```

Figure 2. CLI - Interactive commands

When using the command-line interface, you may be prompted to provide input. When the available updates are displayed, you can select the updates you would like to install. For the update you want to install, type the number of the update and press the ENTER key on the command line. An asterisk '[\*]' will appear in the field next to the update. If you do not want to install the update, retype the number of the update on the command line. A space '[]' will appear in the field next to the update to indicate that the updated is no longer selected. A summary list of the updates is displayed each time a change is made to the selected updates. The other possible commands are: ENTER, a, f, q. Here is a description of each command:

#### number

Typing the number of the update toggles between selecting and deselecting the update. This command displays a summary list of the currently selected updates.

**enter** Pressing the ENTER key by itself re-displays the full update information screen, instead of the summary list of selected updates.

- **a** Apply selected updates.
- f Toggle between selecting and deselecting all updates. This command displays a summary list of the currently selected updates.
- **q** Quit immediately without applying any updates.

The following fields can be displayed on the screen after CLI input:

Table 4. Data displayed on screen after CLI input

Column	Description
Severity	This field displays the importance of an update.
Reboot	This field displays if a reboot is required for updates to take effect and when the reboot should occur if needed.
Update ID	This field displays the name of the update package as downloaded from the IBM web site, without the .xml filename extension.
Update	This field (if shown) displays the name of the individual update contained within the update package. For example the .sys driver file in Windows or the .ko kernel object in Linux.
New Version	If the update is currently uninstalled or undetected, this field displays the version of the overall update package. If the update is detected, this field displays the individual update contained within the update package.
Installed Version	This field displays the version of the individual update that is currently installed on the system.

#### Command processing and general usage notes

Usage notes for UpdateXpress System Pack Installer include command processing and general usage information.

- When using the CLI to invoke the UpdateXpress System Pack Installer GUI, you only need to type an executable filename (in our examples, program> stands in for the executable filename); do not specify an option or command. The GUI can be operated by either a mouse or a keyboard.
- You can use the help or version options by typing them in the CLI with or without a command (example 2 below displays the use of these options without a command).
- Options are processed before commands. Some examples of this behavior are as follows:

Although this command processes the **-local** option first, that option only sets a variable, which goes unnoticed. What you will see is the command returning the version information and exiting before running the update command, because the **-V** option, which exits the program when complete, is processed first.

2. cprogram> -V -h

This command returns the version information and exits before printing the help information or launching the GUI, because the first option to be processed is **-V**, an option that exits the program when complete.

This command returns the help information specific to the acquire command and exits.

This command returns the help information specific to updating BladeCenter components such as the Management Module, I/O Modules and including RSSM.

This command returns the help information specific to the update command and exits.

- Sometimes, an update package applies to a component for which UpdateXpress System Pack Installer cannot determine the system version. In this case, UpdateXpress System Pack Installer displays undetectable for the system version, displays the version of the update package, and selects the package as a recommended update.
- UpdateXpress System Pack Installer does not restart the system for any update. If an update does not take effect until the system is restarted, you must restart the system yourself. Information is displayed to let you know which updates require a restart.

#### Remote functionality

This section provides information about UpdateXpress System Pack Installer remote command-line interface functionality.

You can use the command line interface, on Linux and Windows, to run the compare and update commands on a remote server. The update command is performed in unattended mode. You can use the compare command to view what updates will be applied to the remote system. Remote command execution is logged on the target system. Remote functionality is only supported when source and target systems are the same operating system type, such as Windows-to-Windows or Linux-to-Linux.

All command line options are supported by remote execution. If you wish to only execute a subset of updates you can use the --include and --exclude command line options. Also, --drivers and --firmware command line options can be used to specify a category of updates.

#### Usage examples

#### 

This command acquires the Windows-only updates for an xSeries® 260, model type 8865, and places them in the local folder x3800dir. The folder could also be a networked shared location.

This command compares the updates in the local folder x3800dir with the currently installed version of the firmware and drivers. The results are displayed in a format similar to *Figure 1. CLI - Screen display* in the previous section.

This command forces the application of the driver only updates to the target system identified by IP address 10.2.33.44.

#### Notes and suggestions

The log file is located on the remote target system at:

C:\IBM\_Support\UXSPsystemname\_machinetype\_timestamp.log

(Windows) or at:

/var/log/IBM\_Support/systemname\_machinetype\_timestamp.log

(Linux). *systemname* is the dns name of the system, *machinetype* is the 4-digit Machine Type, and *timestamp* is the time stamp of when the tool was called. Linux syslog or Windows event log, which contain only high-level, predefined strings, register the program> executions on the remote system.

Also note that using the source system as the target system is not supported. Only one instance of the program is allowed per server. Attempting to point the program> to 127.0.0.1 is therefore not a valid scenario.

See "Return codes" on page 58 for more specific program> execution details and troubleshooting information.

# GUI

You can operate the UpdateXpress System Pack Installer through a graphical user interface (GUI).

## Launching the GUI

You can use the CLI to invoke the UpdateXpress System Pack Installer GUI by typing uxspi410.exe or by double-clicking on the **uxspi410.exe** program icon.

**Note:** A screen resolution of 800x600 or higher is recommended when running the GUI. If you must use a resolution of 640x480, the command-line interface is recommended.

# **Acquire Updates**

The Acquire Updates function allows you to download UpdateXpress System Pack(s) and individual updates for supported machine types from a remote location, such as IBM support.

# **Using the CLI**

Use the following information to run the acquire command using the CLI.

# acquire (ac) - acquire updates Format

uxspi410.exe acquire [options]

#### Description

The **acquire** command downloads UpdateXpress System Pack updates or individual updates for supported machine types from the IBM support site.

## **Options**

### --check-update

Checks the Web for a newer version of UXSPI, and downloads it if available.

## -i update-id, --id=update-id

Acquires update specified by update ID. This update ID is the file name of the update without any file extension (for example,

--id=ibm\_fw\_bios\_bce115e\_windows\_i386). If this option is specified, only the update specified by the update ID is downloaded.

### -1 UXSP\_path, --local=UXSP\_path

Specifies the UXSPI directory on the local system where downloaded UXSPs and individual updates are saved. This directory can specify a Windows network share in the format \\server\share or a Linux remote mount point. HTTP and FTP URL-style addresses are not supported.

#### -L, --latest

Acquires the latest individual update instead of UXSPs for the specified machine-types and operating systems. This option also downloads offline updates that match the search criteria of machine-types and operating systems.

### -m type, --machine-type=type

Specifies a list of comma-separated, 4-digit machine types to use for the download criteria. Spaces are not allowed in comma separated values. The machine type must be a number, wild cards are not allowed.

If you specify all, updates for all machine types are downloaded

#### --no-proxy

Specifies to not use a proxy for acquisition. If this value is used with any of the set proxy arguments (--proxy-address, --proxy-port, --proxy-user, --proxy-password) an error message is displayed and error code 10 is returned.

#### -o operating\_systems, --os=operating\_systems

Specifies a list of comma separated operating systems to use for the download criteria (for example, --os=rhel3, rhel5, sles9). The valid operating-systems are: all, none, windows, rhel3, rhel4, rhel5, sles9, sles10, sles11, and vmware. OS independent updates is used to indicate updates for systems that do not have an operating system, such as Management Modules and BladeCenter IO Modules.

If you specify **all**, updates for all operating systems including OS-independent updates are downloaded. If you specify **none**, only OS-independent updates are downloaded.

#### --proxy-address=address

Sets the proxy address setting to address (for example, --proxy-address=10.0.0.10). Address may be either an IP address or a DNS address.

#### --proxy-port=port

Sets the proxy port setting to port. Port must be a number (for example, --proxy-port=40).

#### --proxy-user=user

Sets the proxy user setting to user (for example, --proxy-user=fred).

#### --proxy-password=password

Sets the proxy password setting to password (for example, --proxy-password=passw0rd).

### --proxy-password-secure=password

Sets the secure proxy password setting to password. For example: --proxy-password-secure=STPXR6ygjRIs.

#### -r, --report

Queries the IBM update repository to determine the matching update set, but do not actually download any update. Instead display a list of update-ids, each update-id is displayed on a new line. Those updates that are already present in the UXSPI directory are distinguished from those updates that need to be downloaded. If necessary user can redirect the result of the report to a text file using the shell stdout redirection command. If any part of an update is missing, such as the readme, change history, payload or xml, then it is considered not present for report generation.

**--xml** Specifies that the file ac\_result.xml should be created in the IBM\_Support directory to create summary report files.

# **Using the GUI**

You can use the UpdateXpress System Pack Installer GUI to acquire UpdateXpress System Packs and the latest individual updates.

To acquire updates using the GUI:

- 1. Launch the UpdateXpress System Pack Installer GUI by double-clicking uxspi410.exe.
- 2. See the appropriate task in Chapter 6, "UpdateXpress System Pack Installer scenarios," on page 37

# **Compare and Update**

The Compare and Update functions inventory the system on which the update will be performed, query the update directory for a list of applicable update packages, compare the inventory to the applicable update list, recommend a set of updates to apply, and then deploy those updates to the system.

# Using the CLI

Use the following information to run the compare and update commands using the CLI. The compare and update commands share the same set of command line arguments. The only difference between the compare and the update command is that the compare command stops at the compare step and does not proceed to the update step."

# compare (co) - Compare updates with installed versions Format

uxspi410.exe compare [options]

#### Description

**The compare** command gathers the inventory on the system and queries a specified location. It then compares the data and displays the result.

# update (up) - Apply updates Format

uxspi410.exe update [options]

## **Description**

The **update** command gathers the inventory on the system and queries a specified location. It then compares the data and deploys the recommended set of updates.

# command options

#### -D | --drivers

Applies only driver updates.

#### --disable-imm-lan

Disables the IMM over LAN interface after package installation. You can enable the IMM over LAN interface using device manager for Windows or the ifconfig utility for Linux.

## -e update\_ids, --exclude=update\_ids

Excludes the updates specified by the list of comma separated update IDs (for example, -e ibm\_lib\_mlayr\_vap914a\_winsrvr\_x86-64). It is an error to specify the same update-id in both a --include and --exclude options. If a fix ID specified in update IDs cannot be found, an error is displayed, and UXSPI exits without deploying any updates. You can use this option with the --latest option. You can use this option to customize the content of a UXSP and exclude specific updates from a UXSP. If excluded updates has earlier versions in the UXSPI directory that are in the same supersede chain, the latest update in the supersede chain will be included. The value of update IDs might be all. This is useful when used in conjunction with the -i option and only applies those updates specified by -i.

#### **-f** *update\_ids***, --force=***update\_ids*

Specifies that if the update is run, the installer applies the update even if it means back-leveling the system. At this time, not all updates support running an update in 'force' mode. Use the --include option to apply the 'force' function to either all or a comma delimited list of updates. When not supported by an update, specifying the 'force' is no different than specifying the no force argument. Note that this argument doesn't specify whether the update is selected to be run. The decision to select the update is determined by the version comparison check, or by specifying the --select argument.

## -F | --firmware

Applies only firmware updates.

**Note:** The **--firmware** option does not install or upgrade any drivers, even if the driver is required as a prerequisite.

## --ignore-undetected=update\_ids

Does not apply updates for undetected update IDs (for example, --ignore-undetected=all). You can use this option to prevent installing device drivers or applying firmware on undetected hardware. The value of update IDs can be all. The updates that are ignored are not displayed in the comparisons.

#### -i update\_ids, --include=update\_ids

Includes the updates specified by the list of comma separated update IDs (for example, -i ibm\_lib\_mlayr\_vap914a\_winsrvr\_x86-64). More recent

versions of the included update are not deployed; that is, subsequent updates in the supersede chain are not included. However, if update IDs contains two or more updates belonging to the same supersede chain, an error 36 is returned with a message displayed and no update is deployed. It is an error to specify the same update ID in both a --include and **--exclude** option. You can use this option to customize the content of a UXSP or used with the --latest argument. If this --include option is used with a UXSP, the fix ID that it supersedes in the UXSP is automatically excluded from the list of updates deployed. This argument has higher priority than --drivers and can be combined with --drivers to include a specific firmware update. Similarly --include has higher priority than --firmware and can be used to include a specific driver update. It is an error to include a fix ID that does not exist in the local update directory.

#### -1 UXSP | --local=UXSP

Specifies the path and name of a UpdateXpress System Pack XML file or the directory (on either a shared network or on the local system) in which to search for an applicable UpdateXpress System Pack XML file. This can also specify a Windows network share in the format \\server\share. HTTP and FTP URL-style addresses are not supported.

#### -L | --latest

Applies the latest updates whether the latest updates are from a UXSP, individual updates or a combination of UXSP and individual updates. If this option is not specified, latest UXSP update found in the UXSPI directory are applied.

#### -n | --new

Selects all updates that are either newer than the currently installed versions or are undetected. This includes updates where updateSelection=never in the update XML (Qlogic and Emulex) that are not normally selected for update by default. This has the effect of making the Qlogic/Emulex update behave like other updates.

#### --noinventory

Performs minimal inventory that just gets the machine-type and OS.

#### --nouxsp

Does not deploy UXSPs. If this option or the --latest option is not specified, the default behavior is to automatically deploy a UXSP. The --nouxsp option is particularly useful when used in conjunction with --include option. In that case, only those updates specified by --include are deployed. The specified options must result in at least one update in the compare or update list; otherwise, an error is generated.

#### -o update\_ids | --linux-override=update\_ids

Applies the Linux driver override command to the list of comma separated update IDs (for example, -0 all). Only effects Linux drivers. Deploy Linux drivers with the --update -override options instead --update-force-if**overridden**. This causes drivers to be updated even if the current driver was distributed with the Linux distribution. If a fix ID specified in update IDs cannot be found, a warning is displayed, but UXSPI continues to complete the compare or update command. Update IDs can have the value all, which means the override command should be applied to all Linux drivers.

## --remote=remote\_address

Runs the **update** command on a remote server that is identified by the specified address. The address can be a DNS name or an IP address (for example --remote=10.0.0.1). Do not prefixed the address by "//" characters. The remote update function is supported only in unattended mode.

#### --remote-dir=directory

Sets the staging or working directory of the remote server (for example, --remote-dir=c:\tmp).

## --remote-password=password

Sets the password to the specified password when authenticating with the remote server (for example, --remote-password=UXSPI0). If --remote-user is specified but --remote-password or --remote-password-secure are not specified, you will be prompted to enter a password, which is not echoed to the console. If this option is specified the --remote option must also be specified. Specify --remote-password with no value to pass an empty password.

### --remote-password-secure=secure-password

Sets the secure password to the specified password when authenticating with the remote server (for example, --remote-password-secure=UXSPI0). If --remote-user is specified but --remote-password or --remote-password-secure are not specified, you will be prompted to enter a password, which is not echoed to the console. If this option is specified the --remote option must also be specified. Specify --remote-password-secure with no value to pass an empty password.

#### --remote-user=user

Sets the username to user when authenticating with the remote server (for example, --remote-user=admin). If none is specified the current username is used. If this option is specified the --remote option must also be specified.

# -r | --report

Displays a summary report of updates used for the compare step. The summary report displays the fix ID, description and whether the update would be deployed for each update. Because nothing is actually deployed, this option behaves the same for the **compare** and **update** commands.

#### -s update\_ids, --select=update\_ids

Deploys the appropriate set of updates to the target system even if the system version is newer than the update package version (for example, -s brcm\_fw\_nic\_1.0.0\_windows\_32-64). The default behavior is to backlevel uEFI/BIOS, diagnostics and IMM/BMC firmware updates. Other updates do not backlevel the system to an older version. This option overrides that behavior and selects all updates for deployment including Qlogic and Emulex updates. You can specify the all value to select all updates. This is equivalent to the --force option available in UXSP Installer version 1.20/1.21.

**--xml** Specifies that the files co\_result.xml and up\_result.xml should be created in the IBM\_Support directory to create summary report files.

**Note:** The ordering of options is not significant. Therefore, the following command:

This example deploys drivers and the BIOS update specified by the -include option.

# Example: Running the update command on a system running Windows

C:\><program>.exe update --local=uxsp\8850\windows\ -u -s all

This example shows how you can:

- Invoke UpdateXpress System Pack Installer on a local system running Windows. The filepath for location of the UpdateXpress System Pack XML file is:
  - uxsp\8850\windows\
- 2. Issue the **update** command to inventory, query, compare, and deploy updates.
- 3. Select all updates as applicable, regardless of the system version or the available version (-s all).
- 4. Run the updates in unattended mode (-u).

# Example: Running the compare command on a system running Linux

[root@localhost /root/uxsp/8850/rhel4]# ./program> co

This example shows how you can:

- Invoke UpdateXpress System Pack Installer on a local system running Red Hat Linux 4.0. The filepath for the location of the UpdateXpress System Pack XML file is:
  - [root@localhost /root/uxsp/8850/rhel4]# ./
- 2. Run the **compare** (**co**) command to inventory, query, and compare updates.

#### Linux device drivers and UXSPs

The default operation for Linux device drivers is to maintain the Linux distribution certified drivers whenever possible. This means that by default the installer will not apply the Linux device drivers from the UpdateXpress System Pack. To override this behavior you need to specify the --linuxoverride argument with either the update name to override or all to override all linux device drivers. Once a device driver is no longer the same as the Linux distribution certified driver, you no longer need to specify this --linuxoverride on subsequent UpdateXpress System Pack updates.

# **Using the GUI**

You can use the UpdateXpress System Pack Installer GUI to compare and update UpdateXpress System Packs and the latest individual updates.

To compare and install updates using the GUI:

- 1. Launch the UpdateXpress System Pack Installer GUI by double-clicking uxspi410.exe.
- 2. See the appropriate task in Chapter 6, "UpdateXpress System Pack Installer scenarios," on page 37

# **Update BladeCenter**

The **bladecenter** command provides the capability to update the BladeCenter Management Module, the I/O Modules and the RSSM infrastructure.

### Prerequisites for updating RSSM:

- RSSM must be manually set to servicemode. Failure to have RSSM in servicemode causes the OBCL to return an error.
- When updating the RSSM infrastructure, installation of Python (with pexpect package) is a prerequisite.
- On Windows OS, cygwin is also a prerequisite. UXSP Installer must be run from a cygwin shell.

# Acquiring MM and I/O modules

The following table provides information about each switch:

- **Switch name**: Specifies the name of the switch.
- VPDID: Specifies the Vital Product Data identity. You can use the **bladecenter** --scan command to query the MM or AMM for the VPDID of the I/O modules present in the BladeCenter product.
- **POSID**: Specifies the POS identity. You can use the **bladecenter** --scan command to query the MM or AMM for the POSID of the I/O modules present in the BladeCenter product.
- **Updates acquired using UXSPI**: Specifies whether UXSP Installer can acquire updates.
- Package availability: Specifies whether packages are available from the IBM or vendor Web site.

**Note:** UXSPI uses only metadata during acquistion for BladeCenter updates. UXSPI does not require the metadata when deploying the updates on I/O modules.

• **Deployment location**: Specifies whether the update must be installed on an FTP or a TFTP server. If FTP or TFTP is listed in this column, you must have a FTP or TFTP server installed with which the switch can communicate.

Switch name	VPDID	POSID	Updates acquirable using UXSPI	Package availability	Deployment location
Brocade Entry SAN Switch Module	0x0135	0x0004	No <sup>1</sup>	Vendor Web site	FTP server
Brocade Enterprise SAN Switch Module	0x0135	0x0004	No <sup>1</sup>	Vendor Web site	FTP server
Brocade 4Gb 10-port SAN Switch Module	0x0135	0x0009	No <sup>1</sup>	Vendor Web site	FTP server
Brocade 4Gb 20-port SAN Switch Module	0x0135	0x0009	No <sup>1</sup>	Vendor Web site	FTP server
Cisco Systems Intelligent GbE Switch Module	0x0130	0x0003	Yes	IBM Web site	TFTP server or FTP server
Cisco SystemsFiber Intelligent GbE Switch Module	0x0130	0x0007	Yes	IBM Web site	TFTP server or FTP server

			Updates		
Switch name	VPDID	POSID	acquirable using UXSPI	Package availability	Deployment location
IBM Gb Ethernet Switch Module	0x0130	0x0000	Yes	IBM Web site	TFTP server
IBM 2-port Fiber Channel Switch Module	0x0135	0x0000	Yes	Vendor Web site <sup>2</sup>	FTP server
McData 6-port (2Gb) Fiber Channel Switch Module	0x0135	0x0007	Yes	Vendor Web site <sup>2</sup>	FTP server
McData 10-port (4Gb) Fiber Channel Switch Module	0x0135	0x0008	Yes	Vendor Web site <sup>2</sup>	FTP server
McData 20-port (4Gb) Fiber Channel Switch Module	0x0135	0x0008	Yes	Vendor Web site <sup>2</sup>	FTP server
Nortel Layer 2-7 Gb Ethernet Switch Module	0x0130	0x0001	No <sup>1</sup>	Vendor Web site	TFTP server
Nortel Layer 2/3 Copper Gb Ethernet Switch Module	0x0130	0x0005	Yes	Vendor Web site <sup>2</sup>	TFTP server or FTP server
Nortel Layer 2/3 Fiber Gb Ethernet Switch Module	0x0130	0x0006	Yes	Vendor Web site <sup>2</sup>	TFTP server or FTP server
QLogic 2 Gb 6-port Fiber Channel Switch Module	0x0135	0x0005	Yes	Vendor Web site <sup>2</sup>	FTP server
QLogic 10-port 4Gb Fiber Channel Switch Module	0x0135	0x0006	Yes	Vendor Web site <sup>2</sup>	FTP server
QLogic 20-port 4Gb Fiber Channel Switch Module	0x0135	0x0006	Yes	Vendor Web site <sup>2</sup>	FTP server
IBM Server Connectivity Module	0x0130	0x000A	Yes	IBM Web site	TFTP server or FTP server
Cisco 4X Infiniband Switch Module	0x0138	0x0002	Yes	Vendor Web	TFTP server or FTP server
4x Infiniband Pass-thru Module	0x0138	0x0003	Yes	IBM Web site	TFTP server
Nortel 10Gb High Speed Switch Module	0x0130	0x000D	Yes	Vendor Web site <sup>2</sup>	TFTP server or FTP server
Qlogic Infiniband Ethernet Bridge Module	0x0138	0x0004	Yes	Vendor Web site <sup>2</sup>	FTP server
Qlogic Infiniband Fiber Channel Bridge Module	0x0138	0x0005	Yes	Vendor Web site <sup>2</sup>	FTP server
Disk Storage Module (DSM) for BC-S Chassis	0x0183	0x0005	Yes	IBM Web site	TFTP server

Switch name	VPDID	POSID	Updates acquirable using UXSPI	Package availability	Deployment location
SAS Connectivity Module	0x0133	0x0001	Yes	IBM Web site	TFTP server
RAIDed SAS Switch Module	0x0133	0x0002	Yes	IBM Web site	Local system
Nortel 1/10Gb Uplink Ethernet Switch Module	0x0130	0x000E	No <sup>1</sup>	Vendor Web site	TFTP server or FTP server
Cisco Catalyst Switch 3110x	0x0130	0x000B	Yes	IBM Web site	TFTP server or FTP server
Cisco Catalyst Switch 3110G	0x0130	0x000C	Yes	IBM Web site	TFTP server or FTP server
Cisco Catalyst Switch 3012	0x0130	0x0010	Yes	IBM Web site	TFTP server or FTP server
Qlogic 8Gb Fibre Channel Switch Module	0x0135	0x000C	Yes	Vendor Web site <sup>2</sup>	TFTP server or FTP server
Copper pass-through module	0x135	0x03	Yes	IBM Web site	TFTP server
Optical pass-through module	0x135	0x01	Yes	IBM Web site	TFTP server
Intelligent copper pass-through module	0x130	0x0f	No <sup>1</sup>	IBM Web site	TFTP server
Topspin InfiniBand Switch Module	0x0138	0x0001	Yes	IBM Web site	TFTP server or FTP server

#### Notes:

- 1. UXSP Installer does not acquire these files. You must acquire updates from the appropriate vendor or IBM Web site.
- 2. For updates that are hosted on a vendor Web site, UXSP Installer acquires only the readme and metadata. You must acquire updates from the appropriate vendor Web site. In this case, a message similar to the following is displayed that identifies the vendor URL where the update is hosted.

Some of the update packages are hosted on non-IBM web sites. Such web sites are independent of IBM and IBM has no control over the operation  $% \left( 1\right) =\left( 1\right) \left( 1\right) \left($ of these non-IBM we b sites.

The following update packages are not hosted on the following web sites: nt fw bcsw 123-1.5.4.0 anyos noarch hosted on http://www.bladenetwork.net/request?file=549yub

# Using the CLI

Use the following information to run the **bladecenter** command using the CLI.

**Note:** The **bladecenter** command is not supported by the GUI.

# bladecenter (bc) - bladecenter

uxspi410.exe bladecenter [options]

## **Description**

The **bladecenter** provides the capability to update the BladeCenter Management Module, the I/O Modules and the RSSM infrastructure.

### **Options**

#### -s, --scan

Scans the management modules and I/O modules.

#### -m --mm

Updates the firmware for the management module.

-i, --io Updates the firmware for the I/O modules.

#### -c --convert

Converts a response generated by the BladeCenter/UXBC function on the UpdateXpress CD into a batch or sh file.

#### -h, --help

Displays this (help) message.

# Scan-specific options

#### --mm-address=address

Sets the IP address of the management module to the specified address (for example, --mm-address=10.0.0.1). This parameter is mandatory. If it is missed, a syntax error will be presented.

#### --mm-user=user

Sets the user to the user ID of the management module for authentication (for example, --mm-user=admin). This parameter is mandatory. If it is missed, a syntax error will be presented.

# --mm-password=password

Sets the password of the management module to the specified password when authenticating with the management module (for example, --mm-password=UXSPI0). If -s or --scan is specified but -mm-password is not specified, you will be prompted to enter a password, which is not echoed to the console.

# MM-update-specific options

#### --mm-address=address

Set the IP address of the management module to *address* (for example, --mm-address=10.0.0.1). This parameter is mandatory. If it is missed, a syntax error will be presented.

## --mm-user=user

Set the user ID of the management module to *user* when authenticating with the management module. This parameter is mandatory. If it is missed, a syntax error will be presented. Example: --mm-user=admin

# --mm-password=password

Set the password of the management module to *password* when authenticating with the management module. If –s or --scan is specified but –mm-password is not specified the user will be prompted to enter a password, which is not echoed to the console. Example: --mm-password=UXSPI0

-a --all A flag that indicates if the redundant MM will be updated. If -a is specified, both the primary and redundant MM will be updated. If -a is not

specified, the results depend on the MM. For most MM/AMMs (except very old MM1s), the primary MM will automatically update the redundant MM.

### --mm-file=file1

Set the first path and name of the firmware file of the management module. This parameter is mandatory. If it is missed, a syntax error will be presented. Example: --mm-file cnetmnus.pkt

#### --mm-file2=file2

Set the second path and name of the firmware file of the management module. This parameter is used by MM1, but not necessary for AMM. If it is MM1 and this parameter is missed, a syntax error will be presented. Example: --mm-file2 cnetrgus.pkt

## I/O-module-update-specific options

#### --mm-address=address

Sets the IP address of the management module to *address* (for example, --mm-address=10.0.0.1). This parameter is mandatory. If it is missed, a syntax error will be presented.

#### --mm-user=user

Sets the user ID of the management module to *user* when authenticating with the management module. This parameter is mandatory. If it is missed, a syntax error will be presented. Example: --mm-user=admin

### --mm-password=password

Sets the password of the management module to *password* when authenticating with the management module. If –s or --scan is specified but –mm-password or –mm-password-secure are not specified the user will be prompted to enter a password, which is not echoed to the console. Example: --mm-password=UXSPI0

#### --mm-password-secure=secure-password

Sets the secure password of the management module to *secure-password* when authenticating with the management module. If –s or --scan is specified but –mm-password or –mm-password-secure are not specified the user will be prompted to enter a password, which is not echoed to the console. Example: --mm-password-secure=UXSPI0

## --io-bay=bayID

Sets the bay ID of target RSSM or switch to *bayID*. This parameter is mandatory. If it is missed, a syntax error will be presented. Example: --io-bay=1

**-a --all** Updates all I/O modules of the same POSID/VPDID. If this option is not specified, only the module specified by the io-bay is updated.

#### --io-user=user

Sets the password of the switch to the specified user when authenticating with the switch (for example, --io-user=admin).. If -i or --io is specified but --io-user is not specified, you will be prompted to enter a user name.

#### --io-password-secure=secure-password

Sets the secure password of the switch to the specified password when authenticating with the switch (for example, --io-password=UXSPI0). If -i or --io is specified but --io-password or -io-password-secure are not specified, you will be prompted to enter a password, which is not echoed to the console.

## --io-password=password

Sets the password of the switch to the specified password when authenticating with the switch (for example, --io-password=UXSPI0). If -i or --io is specified but --io-password or -io-password-secure are not specified, you will be prompted to enter a password, which is not echoed to the console.

#### --io-file=file1

Sets the first path and name of the firmware file of the switch (for example, --io-file=tftp://10.10.10.10/GbESM-10G-AOS-1.0.1.1\_OS.img --io-file=ftp://user:pass@10.10.10.10/GbESM-10G-AOS-1.0.1.1\_OS.img). Some switches only support FTP downloading, while others support TFTP downloading, but the path takes a similar syntax: - scheme://username:password@server/path. TFTP does not need a user name and password. If you specify the values, they are ignored.

### --io-file2=file2

Sets the second path and name of the firmware file of the switch (for example, --io-file2=tftp://10.10.10.10/GbESM-10G-AOS-1.0.1.1\_OS.img --io-file2=ftp://user:pass@10.10.10.10/GbESM-10G-AOS-1.0.1.1\_OS.img). Some switches only support FTP downloading, while others support TFTP downloading, but the path takes a similar syntax: - scheme://username:password@server/path. TFTP does not need a user name and password. If you specify values, they are ignored.

# **Convert-specific options**

## --response=response\_file

Sets the path and name of the response file to the specified file name (for example, --response =d:\chassis.rsp).

## --script=script\_file

Sets the path and name of the generated script file to the specified file name (for example, --script = d:\chassis.bat). Currently passwords are scrambled in the response file. The software unscrambles these passwords when creating the batch/sh files. The passwords appear in clear text in the batch/sh file.

## **Examples**

```
uxspi410.exe bc -h
uxspi410.exe bc -s --mm-address=10.0.0.1 --mm-user=USERID --mm-password=PASSW0RD
uxspi410.exe bc -m --mm-address=10.0.0.1 --mm-user=USERID --mm-password=PASSW0RD
    --mm-file=c:\CNETBRUS.pkt --mm-file2=c:\CNETMNUS.pkt
uxspi410.exe bc -i --mm-address=10.0.0.1 --mm-user=USERID --mm-password=PASSW0RD
    --io-bay=1 --io-user=USERID --io-password=PASSW0RD --io-file=
    tftp://10.10.10.10/GbESM-10G-AOS-1.0.1.1_OS.img
uxspi410.exe bc -c --response=d:\chassis.rsp -script=d:\chassis.bat
```

# **Chapter 6. UpdateXpress System Pack Installer scenarios**

You can use UpdateXpress System Pack Installer to interactively or non-interactively deploy updates.

# Updating a local machine from the IBM Web site

UpdateXpress System Pack Installer can update a local machine with either UXSP(s) or individual updates acquired from an IBM Web site.

# **Assumptions and prerequisites**

- 1. The user is running the UpdateXpress System Pack Installer on the local system to be updated.
- 2. The system must be running a supported operating system.

### Scenario tasks

- 1. Launch the UpdateXpress System Pack Installer GUI by double-clicking uxspi410.exe.
- 2. The initial panel describes the UpdateXpress System Pack Installer. Click Next.

**Tip:** The machine type and operating system for the system running the UpdateXpress System Pack Installer is displayed near the top of the panel. The UpdateXpress System Pack Installer version is also displayed.

- 3. On the Update Task panel, select **Update the local machine**. Click **Next**.
- 4. On the Update Type panel, select the type of updates you would like to acquire. Possible updates are:
  - UpdateXpress System Packs (UXSPs)
  - · Individual updates

### Click Next.

- 5. On the Updates Location panel, select IBM web site. Click Next.
- 6. On the Target Directory panel, specify the directory to which you want to download the updates or accept the default location. Click **Next.**
- 7. On the HTTP Proxy Setting panel, specify the proxy information if required. Click **Next**.
- 8. If you selected to acquire individual updates, the Update Selection panel displays. Select the updates you want and then click **Next**.
- 9. The installer begins acquiring updates.

**Note:** The progress bar indicates that the installer is processing, but does not depict a percentage of progress completed.

- 10. On the Update Recommendation panel, make any desired changes and then click **Next**.
- 11. The Update Execution panel displays while the updates are installed to your local system.
- 12. The Complete panel displays when the updated has completed successfully. Click **Finish**.

# Updating a local machine from a local directory

UpdateXpress System Pack Installer can update a local machine with either UXSPs or individual updates acquired from a local directory.

# **Assumptions and prerequisites**

- 1. The user is running the UpdateXpress System Pack Installer on the local system to be updated.
- 2. The system must be running a supported operating system.

#### Scenario tasks

- 1. Launch the UpdateXpress System Pack Installer GUI by double-clicking uxspi410.exe.
- 2. The initial panel describes the UpdateXpress System Pack Installer. Click Next.

**Tip:** The machine type and operating system for the system running the UpdateXpress System Pack Installer is displayed near the top of the panel. The UpdateXpress System Pack Installer version is also displayed.

- 3. On the Update Task panel, select Update the local machine. Click Next.
- 4. On the Update Type panel, select the type of updates you would like to acquire. Possible updates are:
  - UpdateXpress System Packs (UXSPs)
  - Individual updates

Click Next.

- 5. On the Updates Location panel, select **Check in a local directory**. Browse for different directory if desired. Click **Next**.
- 6. The installer begins acquiring updates.

**Note:** The progress bar indicates that the installer is processing, but does not depict a percentage of progress completed.

- 7. On the Update Recommendation panel, make any desired changes and then click **Next**.
- 8. The Update Execution panel displays while the updates are installed to your local system.
- 9. The Complete panel displays when the updated has completed successfully. Click **Finish**.

# Creating a repository of updates

UpdateXpress System Pack Installer can create a repository of either UXSP(s) or individual updates acquired from the IBM web site.

## Before you begin

#### **Prerequisites:**

- The user is running the UpdateXpress System Pack Installer on the system where the repository is to be created.
- The system must be running a supported operating system.

### About this task

Perform these steps to create an update repository:

#### **Procedure**

- 1. Launch the UpdateXpress System Pack Installer GUI by double-clicking uxspi410.exe.
- 2. The initial panel describes the UpdateXpress System Pack Installer. Click Next.

**Tip:** The machine type and operating system for the system running the UpdateXpress System Pack Installer is displayed near the top of the panel. The UpdateXpress System Pack Installer version is also displayed.

- 3. On the Update Task panel, select **Create a repository of updates**, and then click **Next**.
- 4. On the Update Type panel, select the type of updates you would like to acquire, and then click **Next**. Possible updates are:
  - UpdateXpress System Packs (UXSPs)
  - · Individual updates
- 5. On the Machine Types panel, check the machine types for which you want to acquire updates, and then click **Next**.

#### Tips:

- You can select all the listed machine types by checking the top checkbox in the header.
- You can add and remove machine types from the list using the **Add** and **Remove** buttons. To add a machine type, click **Add** and then specify the machine type. To remove a machine type, first check the machine type in the list and then click **Remove**.
- 6. On the Operating Systems panel, select the operating systems for which you would like to acquire updates.

### Tips:

- If you selected to acquire individual updates, you have the option to choose **OS independent update**.
- Select **OS** independent update for updates that do not run from a particular operating system, such as a Management Module update for a BladeCenter. When acquiring Management Module updates, the machine type of the relevant BladeCenter chassis must be selected as well. In the CLI, use **none** to qualify the **-o** | **--os** option. In the interactive CLI or the GUI, specify **OS** independent update as the OS type.
- 7. On the Target Directory panel, specify the directory to which you want to download the updates or accept the default location. Click **Next**.
- 8. On the HTTP Proxy Setting panel, specify the proxy information if required, and then click **Next**.
- 9. If you selected to acquire individual updates, the Update Selection panel displays. Select the updates you want, and then click **Next**.

**Note:** The progress bar indicates that the installer is acquiring updates, but does not depict a percentage of progress completed. The Complete panel displays when the repository has been created successfully.

10. Click Finish.

# Non-interactive local deployment using CLI

UpdateXpress System Pack Installer can non-interactively deploy updates to a system.

A user needs to non-interactively deploy a package or packages to the local system. He can accomplish this by using a command-line based on properties defined in the package XML or XMLs that are specified in a directory on the local file system.

# **Assumptions and prerequisites**

- 1. User has obtained an UpdateXpress System Pack for his machine type and operating system.
- 2. The system must be running a supported operating system.

### Scenario tasks

- 1. User runs UpdateXpress System Pack Installer from the **update** command from the CLI with options specifying the location on the file system to search for the update packages. An option is specified to non-interactively apply the necessary updates to the local system.
  - An example command for this step would be:
  - C:\uxsp> uxspi410.exe update --local=C:\updates -u
- 2. The user sees status on standard output (stdout) as the application proceeds to read all of the UpdateXpress System Pack XML files in the specified directory to determine which UpdateXpress System Pack is applicable to the system. The UpdateXpress System Pack Installer builds an internal catalog of the available updates as specified by the XML file.
- 3. UpdateXpress System Pack Installer gathers the system inventory, and again the user sees status.
- 4. UpdateXpress System Pack Installer compares the inventory with the update catalog and determines a recommendation of updates to apply.
- 5. UpdateXpress System Pack Installer gives status while it proceeds to sequentially run each applicable update on the local system.
- 6. UpdateXpress System Pack Installer exits with a return code designating whether the updates were successful or not.
- 7. UpdateXpress System Pack Installer logs status to the system logs during operation.

## **Error conditions**

- 1. If the operating system is not supported, the user will see a message explaining this at the start of the UpdateXpress System Pack Installer program, and the user is not allowed to deploy updates. UpdateXpress System Pack Installer exits with an unsuccessful return code.
- If no UpdateXpress System Pack XML file can be found in the specified directory that is supported on the local system machine type and operating system, a message similar to the following is displayed:
   Cannot find UpdateXpress System Pack XML file for this machine type and operating system.
  - **Note:** If the machine type or operating system is not supported by a UXSP, it may still be possible to run updates by specifying Individual Updates. To specify Individual Update, specify the **--latest** or **-L** argument.
- 3. If an individual package has an error during deployment, UpdateXpress System Pack Installer continues with the next update, and sets the return code appropriately for the time when UpdateXpress System Pack Installer eventually exits.

# Interactive local deployment using CLI

UpdateXpress System Pack Installer can interactively deploy updates to a system.

A user needs to interactively deploy a package or packages to the local system. He accomplishes this by using a command-line based on properties defined in the package XML or XMLs that are in a specified directory on the local file system.

# **Assumptions and prerequisites**

- 1. User has obtained an UpdateXpress System Pack for his machine type and operating system.
- 2. The system must be running a supported operating system.

## Scenario tasks

- 1. User runs UpdateXpress System Pack Installer from the command line with options specifying the location on the file system to search for the update packages.
  - An example command for this step would be:
  - C:\uxsp> uxspi410.exe update --local=C:\updates
- 2. The user sees status on stdout as the application proceeds to read all of the UpdateXpress System Pack XML files in the specified directory to determine which UpdateXpress System Pack is applicable to the system. The UpdateXpress System Pack Installer builds an internal catalog of the available updates as specified by the XML file. This catalog gets regenerated on every run of UpdateXpress System Pack Installer.
- 3. UpdateXpress System Pack Installer then gathers the system inventory, and again the user sees status.
- 4. UpdateXpress System Pack Installer compares the inventory with the catalog of available updates and determines a recommendation of updates to apply.
- 5. UpdateXpress System Pack Installer displays the list of all available updates, including description, filename, current version, and new version, severity, an enable or disable field, and a number associated with each update. The recommended updates are already enabled.
- 6. The user can type the number of the update for which they would like to toggle the enable/disable field.
- 7. The user then types **a** to apply the updates. Instructions are on the screen to tell the user to perform this step.
- 8. UpdateXpress System Pack Installer gives status while it proceeds to sequentially run each applicable enabled update on the local system.
- 9. UpdateXpress System Pack Installer displays a screen detailing the final status of all the updates that were applied.
- 10. UpdateXpress System Pack Installer exits with a return code designating whether the updates were successful or not.
- 11. UpdateXpress System Pack Installer logs status to the system logs during operation.

## **Error conditions**

1. If the operating system is not supported, the user will see a message explaining this at the start of the UpdateXpress System Pack Installer program, and the user is not allowed to deploy updates. UpdateXpress System Pack Installer exits with an unsuccessful return code.

- 2. If no UpdateXpress System Pack XML file can be found in the specified directory that is supported on the local system machine type and operating system, a message similar to the following is displayed: .
  - Cannot find UpdateXpress System Pack XML file for this machine type and operating system.
- 3. If an individual package has an error during deployment, UpdateXpress System Pack Installer continues with the next update, and sets the return code appropriately for the time when UpdateXpress System Pack Installer eventually exits.

# **Customizing UpdateXpress System Pack using CLI**

UpdateXpress System Pack Installer can customize an UpdateXpress System Pack by specifying command line arguments.

Suppose the user needs to replace a certain level of BIOS in the UpdateXpress System Pack.

# **Assumptions and prerequisites**

- 1. User has obtained an UpdateXpress System Pack for his machine type and operating system.
- 2. The system must be running a supported operating system.

## Scenario tasks

- 1. User downloads the update that needs to be replaced in the UpdateXpress System Pack, in this case a BIOS update. The update can be downloaded directly from the IBM web site or the installer can be used to acquire the update. Either way the update must be placed in the same directory as the UpdateXpress System Pack.
- 2. User runs UpdateXpress System Pack Installer from the command line with options specifying the location on the file system to search for the update packages. An example command for this step would be:

```
C:\uxsp> uxspi410.exe update --local=C:\updates
    --include=ibm_fw_bios_bwe126a_windows_i386
```

- 3. The user sees status on stdout as the application proceeds to read all of the UpdateXpress System Pack XML files in the specified directory to determine which UpdateXpress System Pack is applicable to the system. The UpdateXpress System Pack Installer builds an internal catalog of the available updates as specified by the XML file. This catalog gets regenerated on every run of UpdateXpress System Pack Installer.
- 4. UpdateXpress System Pack Installer then gathers the system inventory, and again the user sees status.
- 5. UpdateXpress System Pack Installer compares the inventory with the catalog of available updates and determines a recommendation of updates to apply.
- 6. UpdateXpress System Pack Installer displays the list of all available updates, including description, filename, current version, and new version, severity, an enable or disable field, and a number associated with each update. The recommended updates are already enabled.
- 7. The user can type the number of the update for which they would like to toggle the enable/disable field.
- 8. The user then types **a** to apply the updates. Instructions are on the screen to tell the user to perform this step.

#### **Error conditions**

- 1. If the operating system is not supported, the user will see a message explaining this at the start of the UpdateXpress System Pack Installer program, and the user is not allowed to deploy updates. UpdateXpress System Pack Installer exits with an unsuccessful return code.
- 2. If no UpdateXpress System Pack XML file can be found in the specified directory that is supported on the local system machine type and operating system, a message similar to the following is displayed:
  Cannot find UpdateXpress System Pack XML file for this machine type and operating system.
- 3. If an individual package has an error during deployment, UpdateXpress System Pack Installer continues with the next update, and sets the return code appropriately for the time when UpdateXpress System Pack Installer eventually exits.

# **Updating from removable media (non-bootable)**

In UpdateXpress System Pack Installer, you can copy a set of UpdateXpress System Packs to media, such as USB key media or CD, including the version of UpdateXpress System Pack Installer included in each of the UpdateXpress System Packs.

# Before you begin

When mounting the media on a Linux operating system make sure that the exec flag is set on the mounted device. This is especially true for RHEL5, since its default is to mount USB keys with noexec.. Otherwise, you get a permission denied message when you try to execute a program from the mounted device.

**Note:** To work around this on RHEL5, unmount the USB key and mount it with an explicit exec option. For example:

umount /dev/sdc1
mkdir /media/disk
mount -o exec /dev/sdc1 /media/disk

# Updating firmware for an IBM BladeCenter RAID SAS switch module

Use this information to update firmware for an IBM BladeCenter RAID SAS switch module.

# Before you begin

#### **Prerequisites:**

- All persistent alerts must be resolved before updating firmware. View the Active
  Alert List to verify if there are any persistent alerts that require resolution. In
  some instances, a persistent alert might be resolved by updating the firmware.
  Check the Release Notes to determine if there are persistent alerts that are fixed
  in this level of code.
- These following utilities must be installed to your system:
- (Windows only) Microsoft Visual Studio Dynamic Link Libraries
- (Windows only) Cygwin
- Python version 2.5 or higher
- Pexpect

### About this task

Perform these steps to update firmware for an IBM BladeCenter RAID SAS switch modules:

#### **Procedure**

- 1. (Windows only) Install Microsoft Visual Studio Dynamic Link Libraries.
  - a. Download the libraries to a temporary directory from the Web by going to www.microsoft.com/downloads/details.aspx?FamilyId=32BC1BEE-A3F9-4C13-9C99-220B62A191EE&displaylang=en and clicking **Download**.
  - b. Run **vcredist\_x86.exe** in the temporary directory and following instructions in the installation wizard.
- 2. (Windows only) Install Cygwin.

**Tip:** Cygwin is a Linux-like environment for Windows. The command line firmware upgrade tool runs from a Cygwin bash shell.

- a. Download Cygwin to the C:\cyg\_dnld\ directory from the Web at www.cygwin.com/setup.exe.
- b. Run **setup.exe** in the C:\cyg\_dnld\ directory. The Cygwin Setup installation wizard is displayed.
- c. Click Next. The Choose Installation Type page is displayed.
- d. Click **Install from Internet**, and then click **Next**. The Choose Installation Directory page is displayed
- **e**. Accept the default settings, and click **Next**. The Select Local Package Directory page is displayed.
- f. Accept the default settings, and click **Next**. The Select Connection Type page is displayed.
- g. Click **Direct Connection**, and click **Next**. The Choose Download Sites page is displayed.
- h. Select any of the URLs listed in the **Available Download Sites** list, and click **Next**. The Select Packages page is displayed.
- i. Select the following installation packages and then click **Next**.

Category	Package	Minimum version	Description
Devel	gcc-core	3.4.4-3	C compiler
Devel	make	3.81-2	The GNU version of the make utility
Libs	ncurses	5.5-3	Libraries for terminal handling
Net	openssh	5.0p1-1	The openSSH server and client programs
Net	ping	1.0-1	A basic networking tool to test IP network connectivity
Net	inetutils	1.5-4	A common networking client and server
Python	Python	2.5.1-2	An interactive object-oriented scripting language
Web	wget	1.10.2-2	Utility used to retrieve files from the internet using HTTP and FTP

When the installation completes, the Cygwin Setup - Installation Status and Create Icons window is displayed.

- j. Click Finish.
- 3. (Linux only) Install Python 2.5 or greater.

**Tip:** You can download Python from the Web at www.python.org/download/.

- 4. Install pexpect for Python:
  - a. Download pexpect from the Web at pexpect.sourceforge.net/pexpect-2.3.tar.gz.
  - b. Open a bash shell. In Windows, run the Cygwin bash shell icon on your desktop. In Linux, open a terminal session.
  - **c**. From the bash shell, enter the following commands:

```
tar -xzf pexpect-2.3.tar.gz
cd pexpect-2.3
python ./setup.py install
```

- 5. Download the SAS RAID Controller firmware update package.
- 6. Ensure that the update package ibm\_fw\_bcsw\_s0cl-*n.n.n.nnn*\_anyos\_noarch.sh is an executable file. If it is not, enter the following command:

```
chmod +x ibm_fw_bcsw_s0cl-n.n.nnn_anyos_noarch.sh
```

- 7. Place both RAID Controller Modules in service mode:
  - a. Login to either RAID Controller CLI.
  - b. Enter the following command from *one* of the RAID controller modules to place the both RAID controller modules in service mode:

```
shutdown -system -state servicemode
```

- c. Wait for the controllers to reboot.
- d. Log in to one of the RAID Controller CLIs.
- **e**. Verify that both RAID controllers are in service mode by entering the following command:

```
list controller
```

8. Enter one of the following command from a Cygwin bash shell to update firmware:

```
uxspi410.distro bc -i --mm-user=user_id --mm-password=password --mm-address=ip_address --io-bay=io_bay --io-file=/var/ibm_fw_bcsw_s0cl-n.n.nnn_anyos_noarch.sh where:
```

distro Specifies the distribution. For example, use uxspi410.exe for Windows, uxspi410.rhel5 for RedHat 5, or uxspi410.sles10 for SLES10.

user\_id Specifies the user ID of the management module.

password

Specifies the password of the management module.

address Specifies the IP address of the management module.

*io\_bay* Specifies the bay number of either SAS RAID controller.

n.n.n.nnn

Specifies the build number of the update package.

**Tip:** Updating firmware for IBM BladeCenter RAID SAS switch modules takes approximately 30 minutes.

# Acquiring the latest updates for a particular type of update

UXSP Installer can be used to acquire the latest UXSPs or all the latest updates for a particular machine type and operating system.

# Before you begin

It can also be used to acquire the latest update for a particular type of update, as long as you know the update-id (filename) of one of the earlier updates. For example, suppose you wish to acquire the latest BIOS update for machine type 7979, and you already know the filename for an earlier version of the BIOS is ibm\_fw\_bios\_gge134e\_windows\_i386. By specifying an update-id together with the latest option (-L) you can acquire the latest BIOS update for that system.

uxspi410 ac -i ibm\_fw\_bios\_gge134e\_windows\_i386 -L

Or if you just want to see if a new update is available but not actually download the update, specify:

uxspi410 ac -i ibm\_fw\_bios\_gge134e\_windows\_i386 -L --report

# **Chapter 7. Troubleshooting**

Use this section to troubleshoot and resolve problems with UpdateXpress System Pack Installer.

# **Limitations and problems**

The following limitations are applicable to IBM UpdateXpress System Pack Installer.

# AMD Driver Pack current version is always undetectable

UpdateXpress System Pack Installer does not detect the current version of the AMD Driver Pack. The resulting behavior is that the AMD Driver Pack update package will be recommended for deployment on every execution of the UpdateXpress System Pack Installer, regardless of the current version.

# Intel® Driver Pack current version is always undetectable

UpdateXpress System Pack Installer does not detect the current version of the Intel Driver Pack. The resulting behavior is that the Intel Driver Pack update package will be recommended for deployment on every execution of the UpdateXpress System Pack Installer, regardless of the current version.

# UpdateXpress System Pack Installer does not support onboard Intel NIC adapter firmware updates

This limitation applies to some models of the System x3250 M3 and iDataPlex dx360 M3, Intel PCIe adapters 49Y4230 and 49Y4240, and the Intel 10Gb, dual port Ethernet Expansion Card CFFh for IBM BladeCenter, model 42C1810.

## UpdateXpress System Pack Installer automatically selects undetected updates

If UpdateXpress System Pack Installer is not able to detect the current version of the device driver or firmware, but an update is available, then UpdateXpress System Pack Installer will select that update as a recommended update (will always update that component).

# UpdateXpress System Pack Installer always installs the LSI driver

If the hardware for a driver component isn't present in the system or is disabled, the installer will not install the driver. The one exception is for the Windows LSI driver. This driver is always installed. You cannot physically remove the LSI chip because it is a standard component on the planar of the system. However, you can disable it. Thus, even in instances when it is disabled, the UpdateXpress System Pack Installer installs the LSI driver.

# Broadcom NetXtreme firmware update requires version 3.58b or greater of the tg3 driver

The Broadcom NetXtreme firmware update requires version 3.58b or greater of the tg3 driver to support the firmware update process. Version 3.58b or greater of the driver must be loaded and currently running before the firmware update will apply successfully.

## Linux device driver updates require specific packages

The Linux device driver update packs require the following packages to be installed:

- rpm-build, perl, and bash for Redhat Enterprise Linux.
- perl and bash for SuSE Enterprise Linux.

### Linux drivers always undetectable in RHEL3

All Linux drivers display as undetectable from the UpdateXpress System Pack Installer UI in RHEL3. The 2.4 kernel used in RHEL3 does not support reporting the version of the installed drivers using the **modinfo** command. There is no known workaround.

### Broadcom firmware always undetectable in RHEL3

All Broadcom firmware displays as undetectable from the UpdateXpress System Pack Installer UI in RHEL3.

# ServeRAID 8i, 8k/8k-l, 8s, 8e and 7t Firmware is only detected on Windows when the Filter driver is active

Detection of ServeRAID 8i, 8k/8k-l, 8s, 8e and 7t Firmware versions requires a filter driver. This filter driver is installed as part of the ServeRAID Manager. It is also installed whenever the ServeRAID firmware update packages from the UpdateXpress System Packs are installed. The ServeRAID firmware update packages will return an error code when executed without the filter driver installed. The Windows system requires a reboot before this driver becomes active. Re-run the ServeRAID firmware update to complete the update.

# 7e SATA/SCSI HostRAID and 8e SAS/SATA HostRAID controllers are not supported on Windows 2008

7e SATA/SCSI and 8e SAS/SATA HostRAID controllers are not supported on Windows Server 2008 (32bit / 64 bit). In addition, when running UXSPI on Server 2008 R2 to compare or update displays a dialog box stating "Integrated RAID On Chip (IROC) Library has stopped working". You must press "Close the Program" twice for the UXSPI to continue.

# Baseboard Management Controller (BMC) and CPLD firmware updates require IPMI drivers

BMC and CPLD firmware updates require installed and running IPMI drivers. If the IPMI drivers are not running the BMC and CPLD firmware version cannot be detected and the online updates will not install.

# Detection of Integrated Management Module (IMM) firmware version requires IPMI drivers

IPMI drivers are required to detect the installed version of the IMM firmware. If the IPMI drivers are not running, the IMM firmware version cannot be detected. Installation of the IMM firmware update, however, is not dependent on the IPMI driver.

# On IBM System x3655, Baseboard Management Controller (BMC) firmware at level 24a will be reported in hexadecimal (base-16) (18.00) instead of decimal (base-10) (24)

This only applies on x3655 for BMC firmware at level 24a. All other BMC firmware levels will report the correct build/version number. This will not affect future BMC updates since all of the release levels are greater than 18.

# Gathering inventory may take 15 to 20 minutes when Linux Remote Supervisor Adapter II (RSA II) daemon is installed without Linux RSA II card installed

On Linux systems, the gathering inventory phase of the install can take as long as 18-20 minutes when the system has the RSA II daemon installed without having the RSA II card installed. The updates you select will still be applied after the delay in the gathering inventory phase.

# Gathering inventory may be delayed on RHEL3 (32-bit) when applying updates over the network

On RHEL 3 (32-bit) systems, the gathering inventory phase of the installation can take as long as 25 minutes when installing over the network. Updates will still be installed after the delay.

# On Windows, only active and loaded drivers associated with a device are detected

For Windows systems, the UXSP Installer only detects the presence and version information for drivers that are active and loaded. A driver for a device may have been installed, but it won't be detected until the operating system associates the driver with its matching device. Drivers that are not associated with a matching device are not detected.

# Different 'New Version' displayed before and after update

The 'New Version' displayed before and after update may differ if the update is undetectable before updating. If the update is currently uninstalled or undetected, this field displays the version of the overall update package. If the update is detected, this field displays the individual update contained within the update package. The version of the overall update package may be different than the version of the individual update file.

### Offline updates are not deployed

Offline updates are not compared or deployed by UpdateXpress System Pack Installer. Offline updates are legacy firmware updates that cannot be directly applied from the OS.

### x460 / MXE-460 / x3950 is only supported in single node

Multi node support is not available for the x460 / MXE-460 / x3950. If you wish to update an x460 / MXE-460 / x3950 multi node, you must break apart the nodes and update as single nodes.

## Only BIOS versions of QLogic FC firmware are detected

The QLogic Fibre Channel firmware update updates both QLogic FC BIOS and firmware. However, the firmware versions of QLogic Fibre Channel firmware updates are not reported. Only the BIOS versions of the QLogic FC firmware are detected. Comparing the update BIOS version to the installed BIOS version is sufficient to determine if the QLogic firmware is backlevel.

# Only Firmware versions of LSI 1064, 1068 and 1078 firmware updates are detected

The LSI 1064, 1068 and 1078 firmware update updates both LSI BIOS and firmware. However, the BIOS versions of LSI firmware updates are not reported. Only the firmware versions of the LSI firmware are detected.

For example, instead of displaying:

Update : SAS1064 Firmware
New Version : 1.23.81.00
Installed Version : 1.23.81.00

Update : SAS1064 Bios New Version : 6.18.01.00 Installed Version : 6.18.01.00

## Only the firmware version is displayed:

Update : SAS1064 Firmware
New Version : 1.23.81.00
Installed Version : 1.23.81.00

Unable to read inserted CD-ROM while updates are being applied on Windows When applying updates on a Windows system using the UXSP Installer, a CD-ROM that is inserted into the CD-ROM drive cannot be read until all updates have completed. An existing CD-ROM that is in the drive can be read provided it is inserted before the updates start.

# Emulex firmware update requires either the Corekit or the HBA Anywhere application

Detection of Emulex firmware update and deployment of Emulex firmware update require either the Emulex CoreKit or the HBA Anywhere application to be already installed.

Emulex firmware version not detected on Windows when using Emulex Corekit UpdateXpress System Pack Installer cannot detect the Emulex firmware version installed on Windows when the Emulex Corekit is used to install the device driver and utility. For firmware detection to work correctly, you have to install Emulex HBAnyware application utility.

# Emulex firmware and BIOS not detected on 64-bit versions of Windows UpdateXpress System Pack Installer can not detect the versions of Emulex BIOS and firmware when running on 64-bit versions of Windows.

On LS21/LS41, the LSI 1064 onboard cannot be distinguished from expansion card

On the LS21/LS41, the LSI 1064 onboard cannot be distinguished from the LSI 1064 expansion adapter. This means that when running in compare or update mode each installed LSI 1064 adapter will be displayed under each LSI 1064 update that is present. The version comparison will be performed and depending on the versioning, the update may be incorrectly determined to be backlevel and may be selected. The updates themselves can distinguish between the adapters and will flash the correct firmware on each adapter.

# Acquisition of Windows updates does not distinguish between the different versions of Windows

Windows 2000, Windows 2003 and Windows 2008 updates are organized in a single Windows UXSP. Similarly the tool acquires all Windows updates (either UXSP or latest individual) for a given system by selecting the OS of Windows. This means that although Windows updates for a given system can be acquired, there may not be updates for the Windows version of interest. For example the acquired UXSP may support Windows 2000 and Windows 2003, but not support Windows 2008. You may wish to use this UXSP to update on Windows 2008. In that case you will get an error code of 33, "Cannot find UpdateXpress System Pack XML file for this Machine Type and Operating System."

#### There is no built-in timeout for completion of updates

UpdateXpress System Pack Installer doesn't require that updates complete within a certain time period. If an update doesn't end UpdateXpress System Pack Installer will run indefinitely.

# The LSI HBA expansion card is undetectable on HS20 (8843) and LS20 blade servers

The LSI HBA expansion card (LSI 1064) is undetectable on HS20 (8843) and LS20 blade servers. The LSI HBA expansion card update can still be applied even if the installed version is not detected.

### The version number is not reported for the RSA 2 firmware

Only the build ID of RSA 2 firmware is reported. The version number is not reported. For example:

[ ] IBM System x3350 Remote Supervisor Adapter II Update

Severity : Initial Release

: Reboot Required to take effect Reboot Update ID : ibm\_fw\_rsa2\_k3
New Version : 1.00 (K3EP05A) : ibm\_fw\_rsa2\_k3ep05a\_linux\_i386

Installed Version : (K3EP05A)

### The version number is not always reported for Diagnostics

The build number of the Diagnostics is always reported; the version number is not always reported.

## The build number of the BMC and IMM are not always reported

The version number of the Baseboard Management Controller (BMC) or Integrated Management Module (IMM) is always reported; the build number is not always reported.

## 8e SATA Controller will not be detected in Windows 2008 environment.

Don't try to run the update for this adapter because it will fail. This is a limitation with the Adaptec HRCCONF tool.

# ServeRAID BR10i and IBM 3Gb SASHBA v2 add-on cards are not distinguishable.

When running in compare or update mode, when a system can support both of these add-on cards, both updates will be listed separately. If at least one of the cards is installed, the same installed firmware version of the only installed card (or one of two cards installed) will show up under the installed version of both updates listed. The version comparison will be performed and, depending on the versioning, the update may be incorrectly determined to be backlevel and may be selected. The updates themselves can distinguish between the adapters and will flash the correct firmware on each adapter.

#### Second OS image not always updated when using an ICPM card.

If the tftp server is set up on the AMM that the ICPM card is plugged into, UpdateXpress System Pack Installer will update the boot image and only one OS image. You will see the error, "Could not find update file" when the product tries to update the second OS image. The AMM version must be at least BPET42D in order to properly configure the ICPM card.

UXSPI only supports updating two files for legacy Management Modules.

Cobia card on Windows 64-bit will require a 64-bit native build Broadcom CIM provider.

## Device driver update returns code 1603

This indicates a general device driver update problem, such as the current device driver is a higher level than the one available in the update, or the hardware is not present. No further action is required.

#### Firmware update from bootable media is not supported for System x3450

For the System x3450, firmware must be updated from within an installed operating system.

# Update from bootable media is not supported via Brocade 10Gb CNA

For this adapter, updates must be performed within a supported operating system.

# Brocade Fibre Channel firmware updates are not supported from bootable

media Brocade Fibre Channel firmware update such as brcd\_fw\_fc\_8g-2.0.0.0 linux-sysx 32-64 are not supported from bootable media. However Brocade firmware updates will run from online operating systems such as RHEL 5.

Version detection of Brocade firmware updates is not supported, even on the operating systems that support the Brocade firmware update.

# Using Windows Server 2003 with IPv6 requires site-local addresses to provide the file-sharing capabilities required by UXSPI

Therefore link-local and global IPv6 addresses are not supported as remote targets.

# Broadcom TG3 device driver brcm dd nic tg3-3.92n rhel5 32-64 fails to deploy on System x336

The driver can still be deployed manually by following the instructions in the package README file.

### Additional considerations when using VMWare ESX remote functions

In order to use the remote functions of VMWare ESX, you must make the following changes:

#### Enable SSH access for the root user

By default, SSH access is blocked for the root user. To enable it, edit the file /etc/ssh/sshd config to change the value of PermitRootLogin to Yes.

# Open firewall ports on the ESX host to allow access for a service or management agent

By default, the ESX host blocks firewall ports used by the service and management agents. You must open these ports to allow the agent to access the server. To allow access

- 1. Log on to the VI client and select the server from the inventory panel.
- 2. Click the **Configuration** tab and select **Security Profile**.
- 3. Select the SSH Client and SSH Server check box and click **OK**.

## Libusb support must be enabled to allow update of the RSA2 driver on VMWare 4.0

You must enable this support manually prior to running the update. To enable support, run the command esxcfg-module -s libusb support=1 usb.o and then restart the machine for the change to take effect.

# Configure the firewall to allow uEFI/DSA/IMM updates on uEFI/IMM systems

To perform these updates, you must configure the firewall to ensure that the flash utilities can connect to the IMM.

#### On VMware 3.5 systems

- esxcfg-firewall --allowIncoming
- 2. esxcfg-firewall --allowOutgoing
- 3. ifconfig cdceth0 169.254.x.x
- 4. route del -net 169.254.0.0 netmask 255.255.0.0 lo
- 5. Then ping 169.254.95.118 to ensure that you can connect to the IMM using the Ethernet over USB interface.

# For VMware 4.0 systems:

- esxcfg-firewall --allowIncoming
- 2. esxcfg-firewall --allowOutgoing
- 3. esxcfg-vswitch -1
- 4. esxcfg-vswitch -L vusb0 vSwitch0
- 5. ifconfig vswif0 169.254.xxx.xxx netmask 255.255.0.0
- 6. Then ping 169.254.95.118 to ensure that you can connect to the IMM using the Ethernet over USB interface.

## LSI BUS messages appear during inventory gathering

An LSI provider used by the UpdateXpress System Pack Installer to gather LSI adapter data during inventory collection prints many lines of LSI BUS messages to the screen. These messages can be ignored.

# The Intel-based Gigabit Ethernet Drivers for Windows v14.0 does not support Windows Server 2008 R2

The Intel-based Gigabit Ethernet Drivers for Windows (intc\_dd\_nic\_14.0\_windows\_32-64.exe) does not support Windows Server 2008 R2. If you attempt to run this driver, you will get an error stating that the install did not succeed. The driver updates that are in v14.0 are already bundled with Windows Server 2008 R2 so it is not necessary to run this update.

# UXSPI does not provide support for Brocade 8GB Fiber Channel adapters

UXSPI cannot detect Brocade 8GB Fiber Channel data. The update firmware can still be deployed by following the instructions in the firmware readme.

### Attempting to backlevel Broadcom from 2.1.1a shows undetected

Broadcom packages 2.1.0c and earlier cannot determine version data if 2.1.1a has already been applied. However the 2.1.0c packages can still be applied and version detection will be corrected.

### UXSPI Acquisition function requires access through firewall

servers running SLES 11 Service Pack 1.

In order to acquire support files from the IBM web site, UXSPI requires access through the local firewall. You must open HTTP port 80 and HTTPS port 443 in order to use the acquisition function.

ServeRAID B5015 controller not detected on System x3850 X5 with SLES 11 SP1 UXSPI cannot detect the ServeRAID B5015 controller on System x3850 X5

# Workarounds

The following know problems and workarounds are applicable to UpdateXpress System Pack Installer, v4.10.

More than one instance of UXSPI cannot be run at the same time. The error message: Exiting from the current instance is displayed when only one instance of UXSPI is running.

UXSPI uses semaphores to prevent UXSP Installer from running multiple instances at the same time. When UXSP Installer exits ungracefully, the semaphore might not get released, preventing another instance of UXSP Installer from starting.

**Workaround:** Run UXSP Installer from command line with **-semdestroy** option. Then, run UXSP Installer as usual.

## UXSPI does not support running multiple copies of itself

Because only one UXSPI tools should apply updates to a system at a time, UXSPI does not support running multiple UXSPI tools at once. It can be useful, however to run multiple copies of UXSPI for remote systems using the **–remote** argument.

**Workaround:** The following example demonstrates this argument for Windows for simultaneously running remote updates on servers 10.6.9.58 and 10.0 8.137:

```
SET UXSPI_MULTIPLE_INSTANCE=1
start cmd.exe /K uxspi410.exe up --remote=10.6.9.58
--remote-user=administrator --remote-password=passw0rd
start cmd.exe /K uxspi410.exe up --remote=10.0 8.137
--remote-user=administrator --remote-password=passw0rd
```

The following example demonstrates this argument for Linux for simultaneously running remote updates on servers 10.6.9.58 and 10.0 8.137:

```
export UXSPI_MULTIPLE_INSTANCE=1
uxspi410.rhe15 up --remote=10.6.9.58 --remote-user=root
--remote-password=passw0rd > log1.txt 2>err1.txt &
uxspi410.rhe15 up --remote=10.0 8.137 --remote-user=root
--remote-password=passw0rd > log2.txt 2>err2.txt &
```

# Cancelling remote Update System Pack Installer instance might cancel other running Update System Pack Installers

A remote Update System Pack Installer, started using the **--remote** option or from a third party connection package such as Windows Remote Desktop Connection, cannot detect another Update System Pack Installer instance running on the same remote system. Running multiple instances on the same system is supported; however, clicking **Cancel** from the graphical user interface terminates all Update System Pack Installers instances running on the remote system.

**Workaround:** It is preferred that you do not run multiple instances of Update System Pack Installer on the same remote system. If you do, manually check if any other administrators are running Update System Pack Installer before clicking **Cancel**.

# Acquisition of latest updates for a new machine type does not update UXSPI supported machine types list

The list of supported machine types in the UpdateXpress System Pack Installer GUI includes all machine types supported at the time UXSPI was released. New machine types will be added to the list when an UpdateXpress System Pack is released for the new machine type, or when the installer is updated. Acquiring updates for a new machine type does not update the supported machine types list in the GUI.

**Workaround:** Acquire the UpdateXpress System Pack for the new machine type, then restart the GUI to update the supported machine types list. Then acquire the latest updates for the new machine type.

#### Unable to execute UpdateXpress System Pack Installer from USB key

Some Linux operating systems (for example, SLES 10) automatically mount USB devices with the **noexec** parameter. This parameter disallows any user to run a program directory from the mounted device.

Workaround: To run a file from a USB device in this configuration, either copy the entire UXSP to your hard disk drive, and execute from that location, or remount the USB device with the exec parameter. You can accomplish the second option by first unmounting the USB device by issuing: umount /mnt/usbkey as root (assuming /mnt/usbkey is the mount point of your USB device). You can then remount the device by specifying the mount command with the exec parameter. For example: mount /dev/sdb1 /mnt/usbkey -o exec).

### Linux drivers are not active immediately

The Linux device drivers require activation. The UpdateXpress System

Pack Installer loads the new driver into the file system, but the operating system does not use the new driver until it is loaded.

**Workaround:** To modify this behavior, remove the existing driver with the **rmmod** command, and load the new driver with the **modprobe** command. Alternatively, the new driver can become active upon reboot of the system.

Linux LSI Logic SCSI 1020/1030/1064/1068 Controllers are not detected after install The Linux device drivers require activation. The UpdateXpress System Pack Installer loads the new driver into the file system, but the operating system does not use the new driver until it is loaded.

**Workaround:** The mptctl driver must be loaded. Run the **Ismod** command to verify that mptcl is loaded. If it is not loaded, run the following command to load the driver: **modprobe mptctl**.

# Linux version of UpdateXpress System Pack Installer requires compatibility libraries

The 64-bit UXSP Installer requires the compatibility libraries. However, the compatibility libraries are not installed by default in RHEL4. Thus, when you execute the installer, it returns an error that says there is a missing library file.

**Workaround:** Ensure you install the legacy software development packages.

# The path passed to the local path argument (-l or --local) must not exceed 234 characters

The local path argument cannot exceed 234 characters

**Workaround:** Copy the UpdateXpress System Pack to a directory that is less than 234 characters.

Firmware updates for Broadcom network card on Linux or CD/DVD and USB-Key bootable-media are not applied when the network card is not up and active On Linux, a Broadcom network interface controller must be up and active in order for firmware Paiutes to be applied. Also, on Linux and when updating from the bootable-media each network Port must be connected to a switch or router.

**Workaround:** Ensure the network interface controller that you are updating is up and active for each port and connected to a switch or router.

## UXSP Installer does not always start on Linux systems

In rare cases the UXSP installer may fail to successfully start on Linux. In those cases the following error message is sent to stderr:

```
WARNING! This package doesn't appear to match your system. It is likely that it will not properly execute. The following information was determined for your system:

distribution = Red Hat release = 4 processor architecture = Intel 64-bit"
```

Distribution, release and processor architecture will vary to match the Linux system. The installer will return an error code of 1.

**Workaround:** Restart the Installer. It will succeed the next time.

### USB key fails on RHEL5

When a USB key is inserted on RHEL5, by default it is mounted as **noexec**. This means no application can run, including the UpdateXpress System Pack Installer.

**Workaround:** Override the default **noexec** mount option. For example, mount a USB key device of /dev/sdc1 as /media/disk. To do so, perform the following steps:

umount /dev/sdc1
mkdir /media/disk
mount -o exec /dev/sdc1 /media/disk

# User Account Control (UAC) on Windows Vista and Windows Server 2008 prevents the installer from running without popup

The UAC is a security control that will normally prompt the user before running application at a privileged level on Windows Vista and Windows Server 2008.

**Workaround:** To disable this feature for the UpdateXpress System Pack Installer, launch the **uxspi410.exe** command prompt with elevated privileges.

- 1. Right-click **uxspi410.exe** and select **Run as Administrator**.
- 2. Click Yes at the UAC prompt command window.

UpdateXpress System Pack Installer will be launched with a full administrator security token.

# Broadcom firmware is not detected or updated from CD/DVD bootable-media on x3550 system

On x3550 system, the CD/DVD bootable-media may not detect the Broadcom firmware version or successfully apply the firmware update.

**Workaround:** Use USB key instead of CD/DVD bootable-media. Or ensure the Baseboard Management Controller (BMC) is updated to version 1.27 build level GFBT43A or later and reboot the system.

Unable to boot from USB Key bootable-media on systems with onboard SATA drives Systems which only support onboard SATA drives, systems such as x336 and x306m systems, will fail to boot the USB Key bootable-media. Systems using ServeRAID adapters, or with LSI onboard 1064 or higher, will not experience this problem.

**Workaround:** Create a CD bootable-media and apply the firmware updates from CD-ROM instead of the USB key.

# Booting from USB Key bootable-media on a x3755 may display video error messages

When booting from USB Key bootable-media on a x3755 you may see video error messages about the video resolution. The error is displayed for 30 seconds unless you press the Enter key.

Workaround: Ignore this error message.

#### Bootable media might not display all updates in the list view

The Bootable media Text User Interface (TUI) might not display all the updates in the list view when the total number of updates in the list view

exceeds the size of the display screen. This is particularly true for the System x3755 which displays a small screen size in the Bootable media text user interface mode.

Workaround: Toggle to see the full update detail list using the Full View selection.

8GB SanDisk USB key doesn't always mount on RHEL3 and VMware ESX 3 Server On RHEL3 and VMware ESX 3 Server, the 8-GB SanDisk USB key doesn't always mount. However, if you create an 8-GB SanDisk bootable USB key it will successfully boot and update the system from the 8-GB SanDisk USB key.

Workaround: Use a different USB key type, for example a 2-GB SanDisk or a n 8-GB Lexar disk.

## When running latest updates on Linux or VMware stems two RSA 2 Daemon Drivers may be displayed

Applying updates with the **-L** | **--latest** argument may display 2 different RSA 2 Daemon Driver versions in the update list.

Workaround: Clear the older RSA 2 Daemon Driver, or use the -e | --exclude argument to exclude the older driver from the update list

### Unable to view all the update versions on VMware

On the VMware console it is not always possible to view the compete update screen because the updates scroll off the page.

**Workaround:** Redirect the output of the compare command to a file. For example, export to a .txt file by running uxspi410.rhel3 co > output.txt. Then view the file using "more" application or log in remotely using an ssh session to the VMware system and scroll thru the updates on the ssh client.

## User Account Control (UAC) on Windows Vista and Windows Server 2008 may not show the results screen

When logging in as a domain ID and running from the command line, the UAC may cause the UXSP Installer to launch a new command prompt window. This new command prompt window exits when UXSP Installer finishes. This means you will not be able to review the results screen.

**Workaround:** Disable UAC for the command prompt window:

- 1. Right-click the command prompt application (cmd.exe) and select Run as Administrator.
- 2. Click **Continue** at the UAC prompt command window.

This launches the command prompt with the full administrator security token.

## Additional requirements for Windows 2003 remote server updates in IPv6 networks

In order to perform remote server updates of a Windows 2003 server in an IPv6 network, you must perform the following steps:

1. Set up the IPv6 network on the target server. Refer to Miscrosoft Step-by-Step guide at: http://www.microsoft.com/downloads/ details.aspx?FamilyID=fd7e1354-3a3b-43fd-955f-11edd39551d7 &displaylang=en

2. Enable file sharing connections over the IPv6 on the target server. To do this, add a key named DisableStrictNameChecking to the registry: HKEY\_LOCAL\_MACHINE\System\CurrentControlSet\Services\ LanmanServer\Parameters, with type REG DWORD and value=1.

### DSA (diags) firmware is not always installed if the IMM is downlevel

Because the DSA firmware update is run before the IMM firmware update, if the IMM firmware is too downlevel, the DSA firmware update will fail.

**Workaround:** Run the update twice. The first update will bring the IMM firmware to the current level, which will allow the second update to update the DSA firmware. A reboot is not required between the updates.

## Return codes

UpdateXpress System Pack Installer has return codes that you can use to determine if any errors were received during the run of the program. The installer returns zero if the operation is successful and non-zero if there is an error. Reviewing the C:\IBM\_Support\uxsp.log (Windows) and /var/log/IBM\_Support/uxsp.log (Linux) log files to determine exactly what went wrong.

UpdateXpress System Pack Installer logs to the following two locations on every run of the program regardless of the command-line options used:

1. **Linux syslog** or **Microsoft Windows event log**, which contain only high-level, predefined strings. For example:

"[timestamp] - [update description] [update version] was [successfully | unsuccessfully] applied <from UpdateXpress System Pack [UpdateXpress System Pack name] [UpdateXpress System Pack version]>"

2. The **Program trace log file in the IBM\_Support directory**, which contains program information at a much higher level of detail than what goes in the syslog or event log. However, the same strings that get logged to the system log will get replicated here as well. This log file has the same level of detail regardless of the command-line option used. This log file is in text format.

# **UpdateXpress System Pack Installer return codes**

UpdateXpress System Pack Installer issues these return codes to help you troubleshoot problems.

Table 5. UpdateXpress System Pack Installer return codes

Return code	Description			
0	Success.			
1	Generic Failure.			
2	Unsupported Operating System.			
10	Invalid Command Line.			
20	Generic Inventory Failure.			
30	Generic Query Failure.			
31	No updates available for this Operating System.			
32	No updates available for this Machine.			
33	Could not find a UpdateXpress System Pack that matches this machine and operating system.			

Table 5. UpdateXpress System Pack Installer return codes (continued)

Return code	Description			
34	Could not read update package meta-data due to unrecoverable error or invalid UpdateXpress System Pack Installer XML file.			
35	The UpdateXpress System Pack required installer version is greater than the current version of the UpdateXpress System Pack Installer.			
40	Generic Comparison Failure.			
60	Generic Update Failure. One or more updates did not install during deployment.			
61	Update Timeout. One of the updates timed out during deployment.			
70	Unable to connect to the IBM update repository.			
71	Unrecoverable error downloading one or more updates from IBM update repository.			
72	Unable to write file.			
73	Specified UpdateXpress System Pack directory does not exist.			
74	Invalid machine-type specified, must be a 4 digit number.			
75	Invalid OS specified.			
76	No applicable update available for specified machine-type/OS.			
77	Acquisition failed. Content not found in repository.			
78	Cannot create directory.			
79	Illegal combination of command line arguments.			
80	Attempting to include and deploy an update that is superseded by another update.			
100	Unable to authenticate with remote server.			
101	Unable to copy files to remote server.			
102	Unable to connect to the remote server.			
103	Unable to collect remote information.			
104	Unexpected failure executing UpdateXpress System Pack Installer on remote system.			
105	Cannot find matching UpdateXpress System Pack Installer for remote system.			
109	Bladecenter function: Command line parameters are invalid.			
110	Bladecenter function: Unable to connect to Management Module, check Management Module 6090 port is open and network is enabled.			
111	Bladecenter function: The login credentials for the Management Module are invalid. Verify username and/or password and/or IP address.			
112	Bladecenter function: Management Module dot command error.			
113	Bladecenter function: One or more files required to flash the Management Module were not found.			
114	Bladecenter function: One or more files required to flash the Management Module were invalid.			
115	Bladecenter function: The Management Module firmware update files are older than/or equal to the current firmware.			
116	Bladecenter function: Management Module General update failure.			

Table 5. UpdateXpress System Pack Installer return codes (continued)

Return code	Description		
117	Bladecenter function: An invalid I/O module bay was specified.		
118	Bladecenter function: Failed to connect to the I/O module.		
119	Bladecenter function: The login credentials for the I/O are invalid. Verify username and/or password.		
120	Bladecenter function: Unable to find the I/O firmware image.		
121	Bladecenter function: The TFTP/FTP server was not found.		
122	Bladecenter function: The login credentials for the FTP server are invalid. Verify username and/or password.		
123	Bladecenter function: The I/O module firmware image is invalid.		
124	Bladecenter function: I/O General update failure.		
125	Bladecenter function: Response (.rsp) file was not found.		
126	Bladecenter function: Invalid response (.rsp) file specified.		

### UpdateXpress System Pack Installer deployment return values

UpdateXpress System Pack Installer issues these deployment return values upon update deployment completion.

Table 6. UpdateXpress System Pack Installer deployment return values

Update return code	Displayed text	Description	
0	Success	The update completed successfully.	
3	Certified Linux driver is not updated	For Linux device drivers a message is also displayed explaining that the update could not be performed, because the system is currently running a certified driver provided by the Linux distribution. Instructions for overriding the certified Linux driver are also displayed. For Linux firmware and Windows, this is reported as "Install did not succeed".	
171	Not applicable	This update is not applicable to the current system configuration. This usually is the case when the update package for a device driver determines that the hardware that the driver is applicable to is not present in the system.	
172	Prerequisites not met	Update was unable to install because all the prerequisites were not met. The prerequisites may include not having the required software already installed, or the hardware is not configured correctly.	
All other codes	Install did not succeed	The update did not install successfully. This could be the result of an error in the update package, or the update failing during installation. This message is sometimes displayed when all the prerequisites were not me	

**Note:** Update deployment return codes other than "Install did not succeed" are mapped to an UpdateXpress System Pack Installer return code of "0: Success". All

other package return codes will cause the Installer to exit with return code of "60: Generic Update Failure. One or more updates did not install during deployment."

## Chapter 8. Coexistence and compatibility

UpdateXpress System Pack Installer builds upon Dynamic System Analysis code, but has no interactions with other products on the system. If a version of Dynamic System Analysis is installed, UpdateXpress System Pack Installer will coexist without interference.

#### **Notices**

This information was developed for products and services offered in the U.S.A.

IBM may not offer the products, services, or features discussed in this document in other countries. Consult your local IBM representative for information on the products and services currently available in your area. Any reference to an IBM product, program, or service is not intended to state or imply that only that IBM product, program, or service may be used. Any functionally equivalent product, program, or service that does not infringe any IBM intellectual property right may be used instead. However, it is the user's responsibility to evaluate and verify the operation of any non-IBM product, program, or service.

IBM may have patents or pending patent applications covering subject matter described in this document. The furnishing of this document does not grant you any license to these patents. You can send license inquiries, in writing, to:

IBM Director of Licensing IBM Corporation North Castle Drive Armonk, NY 10504-1785 U.S.A.

For license inquiries regarding double-byte (DBCS) information, contact the IBM Intellectual Property Department in your country or send inquiries, in writing, to:

IBM World Trade Asia Corporation Licensing 2-31 Roppongi 3-chome, Minato-ku Tokyo 106-0032, Japan

The following paragraph does not apply to the United Kingdom or any other country where such provisions are inconsistent with local law: INTERNATIONAL BUSINESS MACHINES CORPORATION PROVIDES THIS PUBLICATION "AS IS" WITHOUT WARRANTY OF ANY KIND, EITHER EXPRESS OR IMPLIED, INCLUDING, BUT NOT LIMITED TO, THE IMPLIED WARRANTIES OF NON-INFRINGEMENT, MERCHANTABILITY OR FITNESS FOR A PARTICULAR PURPOSE. Some states do not allow disclaimer of express or implied warranties in certain transactions, therefore, this statement may not apply to you.

This information could include technical inaccuracies or typographical errors. Changes are periodically made to the information herein; these changes will be incorporated in new editions of the publication. IBM may make improvements and/or changes in the product(s) and/or the program(s) described in this publication at any time without notice.

Any references in this information to non-IBM Web sites are provided for convenience only and do not in any manner serve as an endorsement of those Web sites. The materials at those Web sites are not part of the materials for this IBM product and use of those Web sites is at your own risk.

IBM may use or distribute any of the information you supply in any way it believes appropriate without incurring any obligation to you.

Licensees of this program who wish to have information about it for the purpose of enabling: (i) the exchange of information between independently created programs and other programs (including this one) and (ii) the mutual use of the information which has been exchanged, should contact:

IBM Corporation Software Interoperability Coordinator, Department 49XA 3605 Highway 52 N Rochester, MN 55901 U.S.A.

Such information may be available, subject to appropriate terms and conditions, including in some cases, payment of a fee.

The licensed program described in this document and all licensed material available for it are provided by IBM under terms of the IBM Customer Agreement, IBM International Program License Agreement or any equivalent agreement between us.

Any performance data contained herein was determined in a controlled environment. Therefore, the results obtained in other operating environments may vary significantly. Some measurements may have been made on development-level systems and there is no guarantee that these measurements will be the same on generally available systems. Furthermore, some measurements may have been estimated through extrapolation. Actual results may vary. Users of this document should verify the applicable data for their specific environment.

Information concerning non-IBM products was obtained from the suppliers of those products, their published announcements or other publicly available sources. IBM has not tested those products and cannot confirm the accuracy of performance, compatibility or any other claims related to non-IBM products. Questions on the capabilities of non-IBM products should be addressed to the suppliers of those products.

All statements regarding IBM's future direction or intent are subject to change or withdrawal without notice, and represent goals and objectives only.

All IBM prices shown are IBM's suggested retail prices, are current and are subject to change without notice. Dealer prices may vary.

This information is for planning purposes only. The information herein is subject to change before the products described become available.

This information contains examples of data and reports used in daily business operations. To illustrate them as completely as possible, the examples include the names of individuals, companies, brands, and products. All of these names are fictitious and any similarity to the names and addresses used by an actual business enterprise is entirely coincidental.

#### COPYRIGHT LICENSE:

This information contains sample application programs in source language, which illustrate programming techniques on various operating platforms. You may copy, modify, and distribute these sample programs in any form without payment to IBM, for the purposes of developing, using, marketing or distributing application programs conforming to the application programming interface for the operating

platform for which the sample programs are written. These examples have not been thoroughly tested under all conditions. IBM, therefore, cannot guarantee or imply reliability, serviceability, or function of these programs.

Each copy or any portion of these sample programs or any derivative work, must include a copyright notice as follows:

- © your company name) (year). Portions of this code are derived from IBM Corp. Sample Programs.
- © Copyright IBM Corp. \_enter the year or years\_. All rights reserved.

If you are viewing this information softcopy, the photographs and color illustrations may not appear.

#### **Trademarks**

IBM, the IBM logo, and ibm.com are trademarks or registered trademarks of International Business Machines Corp., registered in many jurisdictions worldwide. Other product and service names might be trademarks of IBM or other companies. A current list of IBM trademarks is available on the Web at "Copyright and trademark information" at www.ibm.com/legal/copytrade.shtml.

Microsoft, Windows, Windows NT<sup>®</sup>, and the Windows logo are trademarks of Microsoft Corporation in the United States, other countries, or both.

 $Java^{TM}$  and all Java-based trademarks are trademarks of Sun Microsystems, Inc. in the United States, other countries, or both.

Linux is a trademark of Linus Torvalds in the United States, other countries, or both.

Intel is a trademark of Intel Corporation in the U.S. and other countries.

Other company, product, or service names may be trademarks or service marks of others.

### Glossary

This glossary includes terms and definitions for UpdateXpress System Pack Installer.

To view glossaries for other IBM products, go to the IBM Terminology Web site on the Web at www.ibm.com/ibm/terminology.

#### В

#### **Baseboard Management Controller**

A controller that monitors system platform management events such as fan failure and temperature or voltage increases, and logs their occurrence.

#### Basic Input/Output System (BIOS)

The code that controls basic hardware operations, such as interactions with diskette drives, hard disk drives, and the keyboard.

BIOS See Basic Input/Output System.

#### C

#### CLI See Command-line interface.

#### Command-line interface

A type of computer interface in which the input command is a string of text characters.

#### D

#### deployment

Install of update packages.

#### device driver

A program that provides an interface between a specific device and the application program that uses the device.

#### **Dynamic System Analysis**

An IBM systems management software product that collects and analyzes system information to aid in diagnosing system problems.

#### Ε

#### Ethernet

A packet-based networking technology for local area networks (LANs) that allows multiple access and handles contention by using Carrier Sense Multiple Access with Collision Detection (CSMA/CD) as the

access method. Ethernet is standardized in the IEEE 802.3 specification.

#### Extensible Markup Language (XML)

A standard metalanguage for defining markup languages that is based on Standard Generalized Markup Language (SGML).

#### F

#### firmware

Proprietary code that is usually delivered as microcode as part of an operating system. Firmware is more efficient than software loaded from an alterable medium and more adaptable to change than pure hardware circuitry. An example of firmware is the Basic Input/Output System (BIOS) in read-only memory (ROM) on a PC system board.

#### G

#### GUI See Graphical user interface.

#### Graphical user interface

A type of computer interface that presents a visual metaphor of a real-world scene, often of a desktop, by combining high-resolution graphics, pointing devices, menu bars and other menus, overlapping windows, icons and the object-action relationship.

#### 

#### inventory

To gather information about the system including installed hardware, device driver versions, and firmware levels.

#### Intelligent Peripheral Management Interface

A standard for controlling intelligent devices that monitor a system. It provides for dynamic discovery of sensors in the system and the ability to monitor the sensors and be informed when the sensor's values change or go outside certain boundaries.

# IPMI See Intelligent Peripheral Management Interface.

#### 0

#### online update

An update package that can be applied through the native operating system.

#### P

#### prerequisite (pre-req)

A package that must be installed before another package.

#### U

#### update

An UpdateXpress System Pack consisting of an executable file and an XML description.

### UpdateXpress System Pack

Integration-tested bundle of online firmware and driver updates for each System x and BladeCenter blade server.

#### UpdateXpress System Pack Installer

A software application that applies UpdateXpress System Pack updates to your system.

#### X

XML See Extensible Markup Language.

### Index

### A

accessibility features ix allowable UpdateXpress System Pack users 15 AMD machines 11 applying updates 5

### B

BladeCenter, supported servers 9 bladecenter, updating 30

### C

CLI 15, 16, 23, 25
coexistence 63
command line interface (CLI) 16, 23, 25
command options 23, 25
command processing 21
command-line interface 15, 16
commands 23, 25, 30
compare usage 23, 25
concepts 5
CPLD firmware 6
customization of UpdateXpress System
Pack using CLI 42
customizing UpdateXpress System
Pack 42

### D

deployment 40 deployment return values 60 download UpdateXpress System Pack Installer 5 UpdateXpress System Packs 5 DTD 40

### F

firmware 9

### G

glossary 69 graphical user interface (GUI) 23 GUI 15, 16

### Н

handling a UpdateXpress System Pack as a bundle 6 how UpdateXpress System Pack Installer applies updates 5

incomplete inventory date 6, 21 install required device drivers 6 interactive local deployment using CLI 41 interactively deploying updates 41 introducing UpdateXpress System Pack Installer 1 inventory date 6, 21 invoke UpdateXpress System Pack Installer 15

#### L

Linux device drivers 9

### M

migration 63 missing inventory date 6, 21

### Ν

new in v4.10 xi non-interactive local deployment using CLI 40 non-interactively deploying updates 40

### 0

operating system privileges 15 operating systems, supported 11 options 23, 25

### R

remote commands 22
removable media 43
required device driver installation 6
requirements 9
restarts 21
return codes 58
running UpdateXpress System Pack
Installer 23

### S

scenarios 37
sequential processing of options and commands 16, 23, 25
supported firmware 9
supported hardware components 9
supported Linux device drivers 9
supported Linux operating systems 11
supported operating systems 11
Linux 12
VMware 13
Windows 11

supported Windows device drivers 9 supported Windows operating systems 11 Symantec packages 6

#### Т

troubleshooting 47

### U

unsupported systems 11 update from removable media 43 update usage 23, 25 updates 21 updates that require restart 21 UpdateXpress System Pack 1 UpdateXpress System Pack Installer 1 new features xi UpdateXpress System Pack Installer command processing 21 UpdateXpress System Pack Installer commands 23, 25, 30 UpdateXpress System Pack Installer interface 16 UpdateXpress System Pack Installer options 23, 25 UpdateXpress System Pack Installer scenarios 37 using UpdateXpress System Pack Installer 15 uxspi command 15

### W

what's new xi who can use UpdateXpress System Pack Installer 15 Windows device drivers 9

### X

x86 machines 11

### Readers' Comments — We'd Like to Hear from You

IBM UpdateXpress System Pack Installer User's Guide Version 4.10

We appreciate your comments about this publication. Please comment on specific errors or omissions, accuracy, organization, subject matter, or completeness of this book. The comments you send should pertain to only the information in this manual or product and the way in which the information is presented.

For technical questions and information about products and prices, please contact your IBM branch office, your IBM business partner, or your authorized remarketer.

When you send comments to IBM, you grant IBM a nonexclusive right to use or distribute your comments in any way it believes appropriate without incurring any obligation to you. IBM or any other organizations will only use the personal information that you supply to contact you about the issues that you state on this form.

Comments:

Thank you for your support.		
Send your comments to the address on th	e reverse side of this form.	
If you would like a response from IBM, pl	lease fill in the following information:	
Name	Address	
Company or Organization		
Phone No.	F-mail address	

IBW.

Cut or Fold Along Line

Fold and Tape

Please do not staple

Fold and Tape



Indellaallaalllaaldaaddaalllalaaldadal

NO POSTAGE NECESSARY IF MAILED IN THE UNITED STATES

## **BUSINESS REPLY MAIL**

FIRST-CLASS MAIL PERMIT NO. 40 ARMONK, NEW YORK

POSTAGE WILL BE PAID BY ADDRESSEE

IBM ATTN: Dept DO6A 3039 E CORNWALLIS RD, P.O. BOX 12195 Raleigh, NC USA 27709-2195



Fold and Tape

Please do not staple

Fold and Tape

## IBM

Printed in USA